

“B”

**Recommended Conditions of Approval
and Final Agency Approval Memos**

**PLANNING COMMISSION HEARING – DECEMBER 5, 2018
RECOMMENDED CONDITIONS OF APPROVAL**

**SHEEHY SPECULATIVE LIGHT INDUSTRIAL BUILDING
USE PERMIT #P17-00274-UP
EAST SIDE OF DEVLIN ROAD
APN'S 057-210-037 (SFAP) & 038 (SFAP)**

This Permit encompasses and shall be limited to the project commonly known as Sheehy Speculative Light Industrial Building, located on the east side of Devlin Road, south of Sheehy Creek. Part I encompasses the Project Scope and general conditions pertaining to statutory and local code references, project monitoring and the process for any future changes or activities. Part II encompasses the ongoing conditions relevant to the operation of the project. Part III encompasses the conditions relevant to construction and the prerequisites for a Final Certificate of Occupancy. It is the responsibility of the permittee to communicate the requirements of these conditions and mitigations (if any) to all designers, contractors, employees, and the general public to ensure compliance is achieved.

Where conditions are not applicable or relevant to this project, they shall be noted as "Reserved" and, therefore, have been removed.

When modifying a legally established entitlement related to this project, these conditions are not intended to be retroactive or to have any effect on existing vested rights except where specifically indicated.

PART I

1.0 PROJECT SCOPE

This Permit encompasses and shall be limited to:

- 1.1 Approval of a Use Permit including a Variation to the Development Regulations of Napa Valley Business Park Specific Plan (NVBPSP) for a light industrial building as follows:
 - a. Construction of a 40,085 sf one-story building with approximately 38,020 sf of warehouse area and 2,065 sf of office area;
 - b. On-site parking for 58 vehicles;
 - c. A new driveway on Devlin Road;
 - d. A shared drive aisle with the property to the south;
 - e. A reduction to the width of the landscape planter along the east property to a minimum of 5 to 7-feet; and,
 - f. Other landscape improvements, except along the south property line where there will be no landscaping to accommodate the shared drive aisle.

The building shall be designed in substantial conformance with the submitted site plan, elevation drawings, and other submittal materials and shall comply with all requirements of the Napa Valley Business Park Specific Plan and Napa County Code (County Code). It is the responsibility of the permittee to communicate the requirements of these conditions and mitigations (if any) to all designers, contractors, employees, and the

general public to ensure compliance is achieved. Any expansion of or change in use or alternative locations for fire suppression or other types of water tanks shall be approved in accordance with the County Code and may be subject to the permit modification process.

2.0 STATUTORY AND CODE SECTION REFERENCES

All references to statutes and code sections shall refer to their successor as those sections or statutes may be subsequently amended from time to time.

3.0 MONITORING COSTS

All Staff costs associated with monitoring compliance with these conditions, previous permit conditions, and project revisions shall be borne by the permittee and/or property owner. Costs associated with conditions of approval and mitigation measures that require monitoring, including investigation of complaints, other than those costs related to investigation of complaints of non-compliance that are determined to be unfounded, shall be charged to the property owner or permittee. Costs shall be as established by resolution of the Board of Supervisors in accordance with the hourly consulting rate established at the time of the monitoring and shall include maintenance of a \$500 deposit for construction compliance monitoring that shall be retained until issuance of a Final Certificate of Occupancy. Violations of conditions of approval or mitigation measures caused by the permittee's contractors, employees, and/or guests are the responsibility of the permittee.

The Planning Commission may implement an audit program if compliance deficiencies are noted. If evidence of a compliance deficiency is found to exist by the Planning Commission at some time in the future, the Planning Commission may institute the program at the permittee's expense (including requiring a deposit of funds in an amount determined by the Commission) as needed until compliance assurance is achieved. The Planning Commission may also use the data, if so warranted, to commence revocation proceedings in accordance with the County Code.

PART II

4.0 OPERATIONAL CHARACTERISTICS OF THE PROJECT

Permittee shall comply with the following during operation of the project:

4.1 GROUND WATER MANAGEMENT – WELLS [RESERVED]

4.2 AMPLIFIED MUSIC

There shall be no amplified sound system or amplified music utilized outside of approved, enclosed, buildings.

4.3 TRAFFIC

To the maximum extent feasible, scheduling of reoccurring vehicle trips to and from the site for employees and deliveries shall not occur during peak travel times (4:00 – 6:00pm). All road improvements on private property required per Engineering Services shall be maintained in good working condition and in accordance with the Napa County Roads and Streets Standards.

4.4 PARKING

All parking, driveways, and internal roadways shall comply with the Napa County Road and Street Standards. Parking shall be limited to approved parking spaces only and shall not occur along access or public roads or in other locations. In no case shall parking impede emergency vehicle access or public roads.

4.5 TENANCY CHANGE

- a. Any future change of tenancy within the structure shall require administrative review and approval by the PBES Department prior to occupancy. The permittee shall provide the PBES Department with a written profile of the proposed tenant, including name, present address, phone number, description of proposed use, employees, a list of any hazardous materials, and any other information deemed necessary by the PBES Department. The permittee shall also provide a detailed floor plan of the entire structure identifying the location and square footage of all uses within the structure prior to any new tenancy.
- b. Parking based on the use of the tenant/building shall be provided in compliance with the Napa Valley Business Park (NVBP) prior to issuance of a Final Certificate of Occupancy. Parking shall be provided in accordance with the NVBP upon any change of use and/or tenancy, subject to review and approval by the PBES Director. The installation of parking may be deferred until such time as building tenancy requires, subject to review and approval by the PBES Director. Additional landscaping shall be provided in place of any deferred parking spaces.

4.6 BUILDING DIVISION – USE OR OCCUPANCY CHANGES

Please contact the Building Division with any questions regarding the following:

In accordance with the California Building Code (CBC), no change shall be made in the use or occupancy of an existing building unless the building is made to comply with requirements of the current CBC as for a new building.

4.7 FIRE DEPARTMENT – TEMPORARY STRUCTURES

Please contact the Fire Department with any questions regarding the following:

The permittee and/or designee shall obtain a tent permit from the Fire Department for any temporary structures utilized for authorized events allowed per COA No. 1.0 above.

4.8 NAPA COUNTY MOSQUITO ABATEMENT PROGRAM **[RESERVED]**

4.9 GENERAL PROPERTY MAINTENANCE – LIGHTING, LANDSCAPING, PAINTING, OUTDOOR EQUIPMENT STORAGE, MECHANICAL EQUIPMENT, AND TRASH ENCLOSURE AREAS

- a. All lighting shall be permanently maintained in accordance with the lighting and building plans approved by the County.

- b. All landscaping shall be permanently maintained in accordance with the landscaping approved by the County.
- c. All outdoor screening, storage, mechanical equipment and utility structures shall be permanently maintained in accordance with the landscaping and building plans approved by the County. No stored items shall exceed the height of the screening. Exterior equipment shall be maintained so as to not create a noise disturbance or exceed noise thresholds in the County Code.
- d. The colors used for the roof, exterior walls and built landscaping features of the project shall be limited to earth tones that will blend the facility into the colors of the surrounding site specific vegetation. The permittee shall obtain the written approval of the Planning Division prior to any change in paint color that differs from the approved building permit. Highly reflective surfaces are prohibited.
- e. Designated trash enclosure areas shall be made available and properly maintained for intended use.

4.10 NO TEMPORARY SIGNS

Temporary off-site signage, such as “A-Frame” signs are prohibited.

4.11 COMPLIANCE WITH OTHER DEPARTMENTS AND AGENCIES - OPERATIONAL CONDITIONS

The attached project conditions of approval include all of the following County Divisions, Departments and Agencies’ requirements. Without limiting the force of those other requirements which may be applicable, the following are incorporated by reference as enumerated herein:

- a. Engineering Services Division operational conditions as stated in their Memorandum dated April 10, 2017.
- b. Environmental Health Division operational conditions as stated in their Memorandum dated November 16, 2018.
- c. Building Division operational conditions as stated in their Memorandum dated July 7, 2017.
- d. Department of Public Works operational conditions as stated in their Memorandum dated November 26, 2018.
- e. Fire Department operational conditions as stated in their Memorandum dated August 14, 2017.
- f. City of American Canyon operational conditions as stated in their “will serve” letter dated December 1, 2017 (date stamped January 23, 2018).

- g. Napa Sanitation District operational conditions as stated in their “will serve” letter dated August 1, 2017, and their comment letter dated August 17, 2017.

The determination as to whether or not the permittee has substantially complied with the requirements of other County Divisions, Departments and Agencies shall be determined by those County Divisions, Departments or Agencies. The inability to substantially comply with the requirements of other County Divisions, Departments and Agencies may result in the need to modify this permit.

- 4.12 OPERATIONAL MITIGATION MEASURES **[RESERVED]**
- 4.13 OTHER CONDITIONS APPLICABLE TO THE OPERATIONAL ASPECTS OF THE PROJECT **[RESERVED]**
- 4.14 PREVIOUS CONDITIONS **[RESERVED]**

PART III

5.0 PREREQUISITE FOR ISSUANCE OF PERMITS

5.1 PAYMENT OF FEES

No building, grading or sewage disposal permits shall be issued or other permits authorized until all accrued planning permit processing fees have been paid in full. This includes all fees associated with plan check and building inspections, associated development impact fees established by County Ordinance or Resolution, and the Napa County Affordable Housing Mitigation Fee in accordance with County Code.

6.0 GRADING/DEMOLITION/ENVIRONMENTAL/BUILDING PERMIT/OTHER PERMIT PREREQUISITES

Permittee shall comply with the following with the submittal of a grading, demolition environmental, building and/or other applicable permit applications:

6.1 COMPLIANCE WITH OTHER DEPARTMENTS AND AGENCIES - PLAN REVIEW, CONSTRUCTION AND PREOCCUPANCY CONDITIONS

The attached project conditions of approval include all of the following County Divisions, Departments and Agencies’ requirements. The permittee shall comply with all applicable building codes, zoning standards, and requirements of County Divisions, Departments and Agencies at the time of submittal and may be subject to change. Without limiting the force of those other requirements which may be applicable, the following are incorporated by reference as enumerated herein:

- a. Engineering Services Division plan review/construction/preoccupancy conditions as stated in their Memorandum dated April 10, 2017.
- b. Environmental Health Division plan review/construction/preoccupancy conditions as stated in their Memorandum dated November 16, 2018.

- c. Building Health Division plan review/construction/preoccupancy conditions as stated in their Memorandum dated July 7, 2017.
- d. Department of Public Works plan review/construction/preoccupancy conditions as stated in their Memorandum dated November 26, 2018.
- e. Fire Department plan review/construction/preoccupancy conditions as stated in their Memorandum dated August 14, 2017.
- f. City of American Canyon plan review/construction/preoccupancy conditions as stated in their “will serve” letter dated December 1, 2017 (date stamped January 23, 2018).
- g. Napa Sanitation District operational conditions as stated in their “will serve” letter dated August 1, 2017, and their comment letter August 17, 2017.

The determination as to whether or not the permittee has substantially complied with the requirements of other County Divisions, Departments and Agencies shall be determined by those County Divisions, Departments or Agencies. The inability to substantially comply with the requirements of other County Divisions, Departments and Agencies may result in the need to modify the permit.

6.2 BUILDING DIVISION – GENERAL CONDITIONS

Please contact the Building Division with any questions regarding the following:

- a. A building permit shall be obtained for all construction occurring on the site not otherwise exempt by the CBC or any State or local amendment adopted thereto
- b. If there are any existing structures and/or buildings on the property that will need to be removed to accommodate construction activities, a separate demolition permit shall be required from the Building Division prior to removal. The permittee shall provide a “J” number from the Bay Area Air Quality Management District (BAAQMD) at the time the permittee applies for a demolition permit if applicable.
- c. All areas of newly designed and newly constructed buildings, facilities and or site improvements shall comply with the CBC accessibility requirements, as well as, American with Disabilities Act requirements when applicable. When alterations or additions are made to existing buildings or facilities, an accessible path of travel to the specific area of alteration or addition shall be provided, as required per the CBC.

6.3 LIGHTING – PLAN SUBMITTAL

- a. Two (2) copies of a detailed lighting plan showing the location and specifications for all lighting fixtures to be installed on the property shall be submitted for Planning Division review and approval. All lighting shall comply with the CBC.

- b. All exterior lighting, including landscape lighting, shall be shielded and directed downward; located as low to the ground as possible; the minimum necessary for security, safety, or operations; on timers; and shall incorporate the use of motion detection sensors to the greatest extent practical. All lighting shall be shielded or placed such that it does not shine directly on adjacent properties or impact vehicles on adjacent streets. No flood-lighting or sodium lighting of the building is permitted, including architectural highlighting and spotting. Low-level lighting shall be utilized in parking areas as opposed to elevated high-intensity light standards.

6.4 LANDSCAPING – PLAN SUBMITTAL

- a. Two (2) copies of a detailed final landscaping and irrigation plan, including parking details, shall be submitted with the building permit application package for the Planning Division’s review and approval prior to the issuance of any building permit associated with this permit. The plan shall be prepared pursuant to the Water Efficient Landscape Ordinance (Chapter 18.118 of the County Code) requirements in effect at the time of building permit application submittal, as applicable, and shall indicate the names and locations of all plant materials to be used along with their method of maintenance.
- b. Plant materials shall be purchased locally when practical, and, to the greatest extent possible, the plant materials shall be the same native plants found in Napa County. The Agricultural Commissioner’s office shall be notified of all impending deliveries of live plants with points of origin outside of Napa County.
- c. No trees greater than 6” diameter at breast height shall be removed, except for those identified on the submitted site plan. Trees to be retained shall be protected during construction by fencing securely installed at the outer most dripline of the tree or trees. Such fencing shall be maintained throughout the duration of the work undertaken in connection with development/construction. In no case shall construction material, debris or vehicles be stored in the fenced tree protection area.
- d. All landscaped areas and sidewalks shall be separated from parking and drive aisle areas by a minimum 6 inch raised concrete curb. The irrigation system shall utilize reclaimed water. Two feet of required parking stall depth may overhang into non-required landscape planters and sidewalks. Standard sized parking stalls are required to have a minimum depth of 19 feet, and compact stalls may be 16 feet. A maximum of 35% of the parking stalls may be compact.
- e. The irrigation system shall utilize reclaimed water when it is made available in the vicinity. Any undeveloped portion of the property shall be hydro-seeded or an approved equivalent and permanently maintained.

6.5 COLORS

Exterior finishes and colors of the building, roof, parking lot and walkways shall be subject to approval by the Planning Division in conjunction with building permit review and/or prior to painting. Highly reflective surfaces are prohibited.

6.6 OUTDOOR STORAGE/SCREENING/UTILITIES

Details of outdoor storage areas and structures shall be included on the building and landscape plans. No outdoor storage is permitted as part of this action. Any proposal for outdoor storage and proposed screening is subject to separate review and approval by the PBES Department. New utility lines required for this project shall be placed underground.

6.7 MECHANICAL EQUIPMENT

a. Roof mounted equipment shall be screened by a parapet wall of equal or greater height than the highest piece of roof mounted equipment or vent. Equipment may be screened by a separate roof screen that is architecturally integrated with the building if screening by a parapet wall is not feasible or is architecturally undesirable. When separate roof screens are used, roof equipment should be organized into major groups screening a smaller number of units rather than multiple areas. The PBES Director may approve exceptions for solar equipment. All screening is subject to review and approval by the PBES Director. Any skylights shall be subject to review and approval by the PBES Director prior to the issuance of building permits.

b. The term "equipment" includes roof mounted equipment or vents, electrical equipment, gas meter, communication antennas, irrigation valves, storage tanks, or other mechanical equipment. The manner of screening shall be as follows: Communications equipment, including microwave equipment, may remain unscreened if visually integrated with the building design through color, location, and construction; all building mounted equipment, including but not limited to louvers, pipes, overhead doors or service doors, access ladders, downspouts, conduit, and electrical/service boxes, shall be painted consistent with the color scheme of the building.

c. Ground mounted equipment shall be screened by walls or landscaping to the satisfaction of the PBES Director.

d. Exterior equipment shall be located, enclosed or muffled so as not to exceed noise thresholds in the County Code.

6.8 TRASH ENCLOSURES

a. The permittee shall provide one or more trash enclosures (decorative masonry or equivalent), the design of which shall be compatible with the architecture of the project. The enclosure shall be reasonably accessible to employees. A minimum 8' x 10' thickened paving section shall be provided in front of each enclosure. The PBES Director shall approve the design and location of each enclosure. All trash bins shall be stored

within approved trash enclosures. The enclosure shall also include a separate pedestrian walk-in access.

- b. The permittee shall provide adequate, accessible, and convenient areas for the collection and loading of recyclable materials generated by the development. These areas shall be located adjacent to trash enclosures when practical. All recyclable materials areas shall be accessible by collection vehicles. The PBES Director shall approve the design and location of each collection and loading area.

6.9 BICYCLE PARKING

Bicycle parking areas shall be provided at a ratio of one bicycle parking space for every 25 employees, as applicable. At least one bicycle parking space shall be provided.

6.10 CONSTRUCTION CRANES

Any crane used in the construction of the phases shall be lighted and have flags for improved visibility from aircraft; no crane shall exceed 80 feet in height without first obtaining the Federal Aviation Administration's express approval.

6.11 AIRCRAFT OVERFLIGHT EASEMENT

Upon building permit submittal, the permittee shall submit verification that an aircraft overflight easement has been recorded on the property that provides for the right of aircraft operation, overflight and related noises, and for the regulation of light emissions, electrical emissions, or the release of substances such as steam or smoke which could interfere with aircraft operations.

6.12 ADDRESSING

All project site addresses shall be determined by the PBES Director, and be reviewed and approved by the United States Post Office. The PBES Director reserves the right to issue or re-issue an appropriate situs address at the time of issuance of any building permit to ensure proper identification and sequencing of numbers. For multi-tenant or multiple structure projects, this includes building permits for later building modifications or tenant improvements.

6.13 HISTORIC RESOURCES **[RESERVED]**

6.14 DEMOLITION ACTIVITIES **[RESERVED]**

6.15 PERMIT PREREQUISITE MITIGATION MEASURES **[RESERVED]**

6.16 PARCEL CHANGE REQUIREMENTS **[RESERVED]**

6.17 FINAL MAPS **[RESERVED]**

6.18 OTHER CONDITIONS APPLICABLE TO THE PROJECT PERMITTING PROCESS **[RESERVED]**

7.0 PROJECT CONSTRUCTION

Permittee shall comply with the following during project construction:

7.1 SITE IMPROVEMENT

Please contact Engineering Services with any questions regarding the following:

a. GRADING & SPOILS

All grading and spoils generated by construction of the project facilities shall be managed per Engineering Services direction. Alternative locations for spoils are permitted, subject to review and approval by the PBES Director, when such alternative locations do not change the overall concept, and do not conflict with any environmental mitigation measures or conditions of approval.

b. DUST CONTROL

Water and/or dust palliatives shall be applied in sufficient quantities during grading and other ground disturbing activities on-site to minimize the amount of dust produced. Outdoor construction activities shall not occur when average wind speeds exceed 20 mph.

c. AIR QUALITY

During all construction activities the permittee shall comply with the most current version of BAAQMD Basic Construction Best Management Practices including but not limited to the following, as applicable:

1. Post a publicly visible sign with the telephone number and person to contact at the lead agency regarding dust complaints. The BAAQMD's phone number shall also be visible.
2. Water all exposed surfaces (e.g., parking areas, staging areas, soil piles, grading areas, and unpaved access roads) two times per day.
3. Cover all haul trucks transporting soil, sand, or other loose material off-site.
4. Remove all visible mud or dirt tracked onto adjacent public roads by using wet power vacuum street sweepers at least once per day. The use of dry power sweeping is prohibited.
5. All vehicle speeds on unpaved roads shall be limited to 15 mph.
6. All roadways, driveways, and sidewalks to be paved shall be completed as soon as possible. Building pads shall be laid as soon as possible after grading unless seeding or soil binders are used.
7. Idling times shall be minimized either by shutting off equipment when not in use or reducing the maximum idling time to five (5)

minutes (as required State Regulations). Clear signage shall be provided for construction workers at all access points.

8. All construction equipment shall be maintained and properly tuned in accordance with manufacturer's specifications. All equipment shall be checked by a certified visible emissions evaluator. Any portable engines greater than 50 horsepower or associated equipment operated within the BAAQMD's jurisdiction shall have either a California Air Resources Board (ARB) registration Portable Equipment Registration Program (PERP) or a BAAQMD permit. For general information regarding the certified visible emissions evaluator or the registration program, visit the ARB FAQ http://www.arb.ca.gov/portable/perp/perpfaq_04-16-15.pdf or the PERP website <http://www.arb.ca.gov/portable/portable.htm>.

d. **STORM WATER CONTROL**

The permittee shall comply with all construction and post-construction storm water pollution prevention protocols as required by the County Engineering Services Division, and the State Regional Water Quality Control Board.

7.2 **ARCHEOLOGICAL FINDING**

In the event that archeological artifacts or human remains are discovered during construction, work shall cease in a 50-foot radius surrounding the area of discovery. The permittee shall contact the PBES Department for further guidance, which will likely include the requirement for the permittee to hire a qualified professional to analyze the artifacts encountered and to determine if additional measures are required.

If human remains are encountered during project development, all work in the vicinity must be halted, and the Napa County Coroner informed, so that the Coroner can determine if an investigation of the cause of death is required, and if the remains are of Native American origin. If the remains are of Native American origin, the permittee shall comply with the requirements of Public Resources Code Section 5097.98.

7.3 **CONSTRUCTION NOISE**

Construction noise shall be minimized to the greatest extent practical and feasible under State and local safety laws, consistent with construction noise levels permitted by the General Plan Community Character Element and the County Noise Ordinance. Construction equipment muffling and hours of operation shall be in compliance with the County Code. Equipment shall be shut down when not in use. Construction equipment shall be staged, loaded, and unloaded on the project site, if at all practicable. If project terrain or access road conditions require construction equipment to be staged, loaded, or unloaded off the project site (such as on a neighboring road or at the base of a hill), such activities only shall occur daily between the hours of 8:00 AM to 5:00 PM.

7.4 CONSTRUCTION MITIGATION MEASURES

- a. BIO-1: If construction would commence anytime during the nesting/breeding season of the Swainson's hawk, northern harrier, ferruginous hawk, Cooper's hawk, white-tailed kite, other raptors, or other bird species listed in the Migratory Bird Treaty Act (typically February 1 through September 30), a preconstruction survey of the project vicinity for nesting birds shall be conducted. This survey shall be conducted by a qualified biologist (experienced with the nesting behavior of bird species of the region) within 14 days prior to the commencement of construction activities that would occur during the nesting/breeding season. The intent of the survey will be to determine if active nests are present within or adjacent to the construction zone within approximately 250 feet (300 feet for raptors). The survey shall also be conducted in accordance with the protocol of the Swainson's Hawk Technical Advisory Committee's (TAC) *Recommended Timing and Methodology for Swainson's Hawk Nesting Surveys in California's Central Valley*. The survey shall commence early in the Swainson's hawk nesting season (late March to early April) and surveys will be conducted within a minimum 0.25-mile radius of the Project area. The surveys shall be timed such that the last survey is concluded no more than two weeks prior to initiation of construction. If ground disturbance activities are delayed following a survey, then an additional pre-construction survey shall be conducted such that no more than two weeks will have elapsed between the last survey and the commencement of ground disturbance activities. If active nests are found in areas that could be directly or indirectly affected by the project, a no-disturbance buffer zone shall be created around active nests during the breeding season or until a qualified biologist determines that all young have fledged. If any active Swainson's hawk nests are found during the survey, CDFW recommends a disturbance buffer of at least a 0.25 mile to avoid a "take" or adverse impacts to Swainson's hawk. No trees or vegetation shall be removed from the project site during the breeding period. The size of the buffer zones and types of construction activities restricted within them should be determined through consultation with the CDFW depending on the species, taking into account factors such as the following:

- Noise and human disturbance levels at the construction site at the time of the survey and the noise and disturbance expected during the construction activity;
- Distance and amount of vegetation or other screening between the construction site and the nest; and
- Sensitivity of individual nesting species and behaviors of the nesting birds.

The buffer zone around an active nest should be established in the field with orange construction fencing or another appropriate barrier and construction personnel should be instructed on the sensitivity of nest areas. The qualified biologist should serve as a construction monitor during those periods when construction activities would occur near active

nest areas of special status bird species to ensure that no impacts on these nests occur.

Method of Mitigation Monitoring: The permittee shall have a nesting bird survey completed prior to any construction activities scheduled to occur on the site from February 1 through September 30. The survey shall also be conducted in accordance with the protocol of the Swainson's Hawk Technical Advisory Committee's (TAC) *Recommended Timing and Methodology for Swainson's Hawk Nesting Surveys in California's Central Valley*. The survey results shall be provided to the Napa County Planning, Building and Environmental Services. In the event any special-status or other protected nesting birds are found to occur on-site construction activities will be scheduled to avoid nesting and breeding periods and consultation will be sought with CDFW to develop appropriate measures to reduce potential impacts to nesting Swainson's hawk which may include preservation of potential foraging habitat.

- b. BIO 2: Prior to the commencement of construction activities during the breeding season of native bat species in California (generally occurring from April 1 through August 15), a qualified biologist shall conduct a focused survey to determine the presence/absence of any special status bat species. If bats are found the following measures will be implemented:
- A plan for removal or exclusion of any tree between October 16 and August 14 will be developed by a qualified biologist in conjunction with the CDFW.
 - Trees that are to be removed between August 15 and October 15 will be trimmed and removed in a two-phased system conducted over two consecutive days under the supervision of a qualified biologist. The first day (afternoon), limbs, branches and trunks without cavities, crevices and deep bark fissures are removed by chainsaw only. Limbs and trunks with cavities, crevices and bark fissures would be avoided. On the second day, the remainder of the tree may be removed.

Method of Mitigation Monitoring: The permittee shall have a bat survey completed prior to any construction activities scheduled to occur on the site. The survey results shall be provided to the Napa County Planning, Building and Environmental Services. In the event bats are found to occur on-site consultation the measures listed above shall be implemented.

- f. BIO 3: Within 48 hours prior to the commencement of construction activities, a qualified biologist shall conduct a preconstruction CRLF survey to ensure that no CRLF are located on or in proximity to the site. If CRLF are found, the CDFW and USFW will be contacted to determine appropriate mitigation measures and the work shall be halted until the consultations are completed.

Method of Mitigation Monitoring: The permittee shall have a CRLF survey completed prior to any construction activities scheduled to occur on the

site. The survey results shall be provided to the Napa County Planning, Building and Environmental Services. In the event CRLF are found to occur on-site consultation will be sought with CDFW to develop appropriate measures to reduce potential impacts CRLF.

- g. BIO 4: Within 48 hours prior to the commencement of construction activities, a qualified biologist shall conduct a preconstruction survey for western pond turtles to ensure that no pond turtles are located on or in proximity to the site. If pond turtles are found, the CDFW will be contacted to determine appropriate mitigation measures and the work shall be placed on hold until the consultation is completed.

Method of Mitigation Monitoring: The permittee shall have a western pond turtle survey completed prior to any construction activities scheduled to occur on the site. The survey results shall be provided to the Napa County Planning, Building and Environmental Services. In the event western pond turtle are found to occur on-site consultation will be sought with CDFW to develop appropriate measures to reduce potential impacts to the turtles.

7.5 OTHER CONSTRUCTION CONDITIONS APPLICABLE TO THE PROJECT PROPOSAL

- a. Prior to any earth disturbing activities, temporary construction fencing shall be placed along the 35-foot setback from Sheehy Creek, measured from the top of bank. The location of the fencing shall be identified on the construction site plan and Civil drawings submitted for building permit review.
- b. Pre-construction meeting: No more than two weeks, or as otherwise specified by project mitigation measures. Prior to the commencement of any vegetation removal, earth-disturbing activities, or other development activities associated with this project, the owner/permittee shall schedule an on-site pre-construction meeting that shall include the project planner, owner or owner's agent, plan preparer, contractor(s), and any other parties deemed necessary by Planning Division staff, such as but is not limited to: County Planning and Conservation Division staff and the project biologist. The purpose of this meeting will be to review the development requirements of #P17-00274-UP including but not limited to: implementation and compliance with project specific conditions of approval and mitigation measures, inspection of stream setback staking/fencing, timing of development activities and pre-construction surveys, and the details of the approved plan. All required protective buffers, including buffer fencing/delineation, shall be installed prior to the pre-construction meeting for inspection by Planning Division staff. Development activities associated with #P17-00274-UP shall not commence until the owner/permittee has received written clearance from the Planning Division indicating that all pre-construction conditions have been satisfied.

8.0 TEMPORARY CERTIFICATE OF OCCUPANCY – PREREQUISITES

A Temporary Certificate of Occupancy (TCO) may be granted pursuant to the County Code to allow specific limited use of the warehouse and office areas prior to completion of all project improvements. Permittee shall comply with the following before a TCO is granted:

8.1 TEMPORARY OCCUPANCY

All life and safety conditions shall be addressed prior to issuance of a TCO by the County Building Official. TCOs shall not be used for general public occupancy of buildings and shall not exceed the maximum time allowed by the County Code which is 180 days. In special circumstances, Departments and/or Agencies with jurisdiction over the project are authorized as part of the TCO process to require a security deposit or other financial instrument to guarantee completion of unfinished improvements.

9.0 FINAL CERTIFICATE OF OCCUPANCY – PREREQUISITES

Permittee shall comply with the following before a Final Certificate of Occupancy is granted by the County Building Official, which upon granting, authorizes all use permit activities to commence:

9.1 FINAL OCCUPANCY

All project improvements, including compliance with applicable codes, conditions, and requirements of all Departments and Agencies with jurisdiction over the project, shall be completed.

9.2 SIGNS

Detailed plans, including elevations, materials, color, and lighting for any project identification or directional signs shall be submitted to the Department for administrative review and approval prior to installation. Administrative review and approval is not required if the signage to be installed is consistent with signage plans submitted, reviewed and approved as part of this permit approval. All signs shall meet the design standards as set forth in the County Code. Any off-site signs allowed shall be in conformance with the County Code.

9.3 GATE/ENTRY STRUCTURES

Any gate installed at the project entrance shall be reviewed by the PBES Department and the Fire Department to assure that the design allows large vehicles, such as motorhomes, to turn around if the gate is closed without backing into the public roadway, and that fire suppression access is available at all times. If the gate is part of an entry structure an additional permit shall be required pursuant to the County Code and in accordance with the Napa County Roads and Street Standards. A separate entry structure permit is not required if the entry structure is consistent with entry structure plans submitted, reviewed, and approved as part of this permit approval.

9.4 LANDSCAPING

Landscaping shall be installed in accordance with the approved landscape plan.

- 9.5 ROAD OR TRAFFIC IMPROVEMENT REQUIREMENTS **[RESERVED]**
- 9.6 DEMOLITION ACTIVITIES **[RESERVED]**
- 9.7 GRADING SPOILS
All spoils piles shall be removed in accordance with the approved grading permit and/or building permit.
- 9.8 MITIGATION MEASURES APPLICABLE PRIOR TO ISSUANCE OF A FINAL CERTIFICATE OF OCCUPANCY **[RESERVED]**
- 9.9 OTHER CONDITIONS APPLICABLE PRIOR TO ISSUANCE OF A FINAL CERTIFICATE OF OCCUPANCY
 - a. The temporary construction fencing placed along the Sheehy Creek setback shall be removed prior to final occupancy.



A Tradition of Stewardship
A Commitment to Service

Planning, Building & Environmental Services

1195 Third Street, Suite 210
Napa, CA 94559
www.countyofnapa.org

David Morrison
Director

MEMORANDUM

To: Sean Trippi, Planning	From: Neil VoPham, Engineering
Date: April 10, 2017	Re: P17-00274 Sheehy Building APN: 057-210-037/038

The Engineering and Conservation division ('Engineering') has reviewed the use permit application P17-00274 for the [Subject] located on assessor's parcel number 057-210-037/038. In general the project proposes the following:

Industrial Building

Based upon the information provided in the application, Engineering finds the application **complete** and recommends the following conditions of approval:

EXISTING CONDITIONS

1. The Existing Parcel is in the Airport Industrial Area

RECOMMENDED APPROVAL CONDITIONS:

OPERATIONAL CHARACTERISTICS

1. Should the existing outdoor/uncovered loading/unloading areas and/or processing areas, including but not limited to wine grape crushing/pressing, juice fermentation, blending and fining, filtration and bottling, be modified, expanded and/or improved in the future, Napa County may require these area to be paved and performed undercover.
2. The facility is designated as a discharger that discharges stormwater associated with industrial activity to waters of the United States. Therefore, the facility shall maintain or apply for coverage under the State Water Resources Control Board's Industrial General Permit (IGP), including meeting all applicable provision and protocols of the IGP. If the facility fails to meet the discharge prohibitions of the IGP, Napa County may require the facility to make the necessary improvements to eliminate all exposures to stormwater of the pollutant(s) for which the water body is impaired.

PREREQUISITES FOR ISSUANCE OF PERMITS

3. Any roadway, access driveway, and parking areas, proposed new or reconstructed shall meet the requirements as outlined in the latest edition of the Napa County Road & Street Standards for Commercial development at the time of use permit approval. The property owner shall obtain a grading permit for all proposed roadway improvements.
4. All on site civil improvements including but not limited to the excavation, fill, general grading, drainage, curb, gutter, surface drainage, storm drainage, parking and drive isles, shall be constructed according to plans prepared by a registered civil engineer, which will be reviewed and approved by the Engineering Division of the Napa County Planning, Building, and Environmental Services Department (PBES) **prior to the commencement** of any on site land preparation or construction. Plans shall be wet signed and submitted with the building and/or grading permit documents at the time of permit application. A plan check fee will apply.
5. Grading and drainage improvements shall be constructed according to the current Napa County Road and Street Standards, Chapter 16.28 of the Napa County Code, and Appendix J of the California Building Code.
6. **Prior to issuance of a building permit** the owner shall submit the necessary documents for Erosion Control as determined by the area of disturbance of the proposed development in accordance with the Napa Countywide Stormwater Pollution Prevention program Erosion and Sediment Control Plan Guidance for Applicant and Review Staff dated December 2014.
7. **Prior to issuance of a building permit** the owner shall prepare a Regulated Project Stormwater Control Plan (SCP) in accordance with the latest edition of the BASMAA Post-Construction Manual for review and approval by the Engineering Division in PBES.
8. **Prior to issuance of a building permit**, an Operation and Maintenance Plan shall be submitted and tentatively approved by the Engineering Division in PBES. **Before final occupancy** the property owner must legally record the "Operation and Maintenance Agreement", approved by the Engineering Division in PBES.
9. All improvements shall conform to the latest Napa County Airport Industrial Area Specific Plan.
10. Applicant shall pay the applicable Napa County Airport Industrial Area Traffic Mitigation Fees prior to receiving any building permits for this project. The applicant should contact the Public Works office to obtain information regarding the determination of this fee.
11. The Applicant must comply with all associated requirements and exhibits relating to water conditions to be imposed on all parcels as described in Napa County Agreement No. 7070, between the County of Napa and the City of American Canyon.

PREREQUISITES DURING PROJECT CONSTRUCTION

12. Required on-site pre-construction meeting with the Napa County PBES Engineering Division **prior to start of construction.**

PREREQUISITES FOR TEMPORARY CERTIFICATE OF OCCUPANCY

13. All roadway improvements shall be completed **prior to execution** of any new entitlements approved under this Use Permit. **** If no temporary occupancy is requested, then this becomes a requirement prior to final occupancy.**

PREREQUISITES FOR FINAL CERTIFICATION OF OCCUPANCY

14. Operations and Maintenance Agreement for post construction Stormwater facilities must be legally recorded.

15. Site shall be completely stabilized to the satisfaction of the County Engineer prior to Final Occupancy.

Any changes in use may necessitate additional conditions for approval.

If you have any questions regarding the above items, please contact Neil VoPham from Napa County Planning, Building, and Environmental Services Department, Engineering and Conservation Division, at (707)299-1358 or by email at Neil.VoPham@countyofnapa.org



A Tradition of Stewardship
A Commitment to Service

Planning, Building & Environmental Services

1195 Third Street, Suite 210
Napa, CA 94559
www.countyofnapa.org

David Morrison
Director

MEMORANDUM

To: Sean Trippi, Project Planner	From: Kim Withrow, Environmental Health Supervisor
Date: November 16, 2018	Re: Sheehy Building APN 057-210-037 & 057-210-038 File #P17-00274

Environmental Health staff has reviewed an application requesting approval to construct a concrete building for possible light manufacturing/industrial, commercial kitchen, office and storage as described and depicted in the application materials. This Division has no objection to approval of the application with the following conditions of approval:

Prior to building permit issuance:

1. If any food or beverage facilities are included in the project, plan review and approval shall be obtained from this Division prior to issuance of any building permits. An annual food permit will be required.
2. The proposed development must be connected to the City of American Canyon water system.
3. All waste water lines of the proposed development must be connected to the Napa Sanitation District.
4. Adequate area must be provided for collection of recyclables. The applicant must work with the franchised garbage hauler for the service area in which they are located, in order to determine the area and the access needed for the collection site. The garbage and recycling enclosure must meet the enclosure requirements provided during use permit process and be included on the building permit submittal. The designated area shall remain available and be properly maintained for its intended use.

During construction and/or prior to final occupancy:

5. During the construction, demolition, or renovation period of the project the applicant must use the franchised garbage hauler for the service area in which they are located for all wastes generated during project development, unless applicant transports their

own waste. If the applicant transports their own waste, they must use the appropriate landfill or solid waste transfer station for the service area in which the project is located.

6. Obtain food permit to operate if necessary.

Upon final occupancy and thereafter:

7. Any hazardous waste produced on site must be stored and disposed of in a manner consistent with Chapter 6.5, Division 20 of the California Health and Safety Code and with Title 22, Division 4.5 of the California Code of Regulations. Additionally, a Hazardous Waste Generator Permit must be obtained from this Division.
8. Pursuant to Chapter 6.95 of the California Health and Safety Code, businesses that store hazardous materials above threshold planning quantities (55 gallons liquid, 200 cubic feet compressed gas, or 500 pounds of solids) shall obtain a permit, file an approved Hazardous Materials Business Plan to <http://cers.calepa.ca.gov/>, and be approved by this Division within 30 days of said activities.
9. All solid waste shall be stored and disposed of in a manner to prevent nuisances or health threats from insects, vectors and odors.



A Tradition of Stewardship
A Commitment to Service

Planning, Building, & Environmental Services

1195 Third Street, Suite 210
Napa, CA 94559
www.co.napa.ca.us

Main: (707) 253-4417
Fax: (707) 253-4336

David Morrison
Director

To: Sean Trippi, Project Planner	From: Marie Taylor, Building Inspector
Date: July 07, 2017	Re: Use Permit – Sheehy Building File # P17-00274 Address: Devlin Road South Napa Napa, Ca. 94558 APN: 057-210-037 & 057-210-038

Building Inspection Division; Planning Use Permit Review Comments

The plans provided for the Use Permit application P17-00274 do not provide enough information in sufficient detail to determine code requirements. A complete plan check will be performed at the time of application and plan submittal to the building division for required permits. The following are provided to prepare the applicant for some standard submittal requirements for the plan review of the building permit process.

Any existing structures and/or buildings on the property that will be demolished require a separate demolition permit issued by The Napa County Building Division prior to demolition. The applicant will be required to provide a J number form Bay Area Air Quality Management District at the time of application for the permit.

The site and associated buildings are required to be accessible to persons with disabilities. This includes but not limited to, parking, accessible path of travel from parking to all buildings and areas on site that are available to employees and the public. Plans must also include all accessibility features for the interior work. An Accessible Upgrade Worksheet must be submitted with plans as a part of the permit process.

Occupant load will determine occupancy types, exiting requirements, and restroom facilities.

Any change in occupancy or use will require building to comply with the requirements of the California Building Code for a new occupancy or use.

Should you have any questions, please contact Marie Taylor at (707) 299-1359



A Tradition of Stewardship
A Commitment to Service

Department of Public Works

1195 Third Street, Suite 101
Napa, CA 94559-3092
www.countyofnapa.org/publicworks

Main: (707) 253-4351
Fax: (707) 253-4627

Steven Lederer
Director

DRAFT MEMORANDUM

To: PBES Staff	From: Ahsan Kazmi, P.E. Senior Traffic Engineer
Date: November 26, 2018	Re: Sheehy Building – Conditions of Approval P17-00274

This memorandum is a follow up of the Public Works Memorandum to PBES dated August 17, 2017, regarding the Sheehy Building. The following conditions are subject to meet before approval of any permit:

Permit Requirements

Street Frontage Improvements Required: The project shall construct improvements along Devlin Road fronting the property, consistent with the Napa Valley Business Park Specific Plan (NVBPSP) design standards for 4-lane collectors and the Countywide Bicycle Plan (CBP), including a minimum 10-foot multi-use path for the full length of the frontage. Improvement plans shall be prepared by a Registered Civil Engineer, in compliance with the NVBPSP, CBP and the Napa County Road & Street Standards, for approval by the Department of Public Works, Road Commissioner. Additional right-of-way shall be dedicated to the public as necessary to encompass the improvements. Improvement plans and right-of-way dedication, if needed, shall be completed prior to the issuance of any permits.

Encroachment Permit Required: An encroachment permit will be required for any improvements in the County's right-of-way. Please contact Patt Throne-Hetzer in the Public Works office at (707) 259-6719 for application submittal information; or Craig Chapin in the Roads office at (707) 944-0196 for technical questions/information.

Completion of improvements and certification shall be completed prior to occupancy or establishment of use. More information is available at our website:

<https://www.countyofnapa.org/2171/Encroachment-Permits>

Traffic Mitigation Fees required: All new development, or improvements to existing development that will generate additional traffic, in the Napa Valley Business Park are required to pay a Traffic Mitigation Fee. The fees collected are used to fund the construction of new roads and intersection improvements in the area. More information on these is available at our website:

<http://www.countyofnapa.org/publicworks/roads>

Please contact me at Ahsan.Kazmi@countyofnapa.org or call (707) 259-8370 if you have questions or need additional information.



A Tradition of Stewardship
A Commitment to Service

Napa County Fire Department
Fire Marshal's Office
Hall of Justice, 2nd Floor
1125 3rd Street
Napa, CA 94559

Office: (707) 299-1461

Garrett Veyna
Fire Marshal

MEMORANDUM

TO: Sean Trippi Planning Division	DATE: August 14, 2017
FROM: Garrett Veyna Fire Department	
SUBJECT: P17-00274	APN: 057-210-037/038

The Napa County Fire Marshal's Office has reviewed the submittal package for the above proposed project. The Fire Marshal approves as submitted and requires the following conditions to be incorporated as part of permit issuance.

1. All construction and use of the facility shall comply with all applicable standards, regulations, codes and ordinances at time of Building Permit issuance.
2. Beneficial occupancy will not be granted until all fire department fire and life safety items have been installed, tested and finalized.
3. Projects shall have an approved water supply for fire protection be made available as soon as combustible material arrives on the site. All underground fire lines, pump and tank plans are required to be a separate submittal from the building or civil plans.
4. **Add note to plan:** Separate submittals required for Underground Fire Lines, Fire Pump, **Automatic Fire Sprinklers, Fire Alarm Systems, Kitchen Hood Extinguishing Systems, High Piled Storage** (any combustible stored over 12 feet in height).
5. All buildings, facilities, and developments shall be accessible to fire department apparatus by way of approved access roadways and/or driveways. The fire access road shall comply with the requirements of the Napa County Road & Street Standards.
6. Access roads shall be designed and maintained to support the imposed loads of fire apparatus and shall be surfaced so as to provide all-weather driving capabilities. Provide an engineered analysis of the proposed roadway noting its ability to support apparatus weighing 75,000 lbs.
7. Provide fire department access roads to within 150 feet of any exterior portion of the buildings as measured by an approved route around the exterior of the building or facility.
8. Roadways shall be a minimum of 20 feet in width with a 2 foot shoulder and 15 foot vertical clearance.



A Tradition of Stewardship
A Commitment to Service

Napa County Fire Department
Fire Marshal's Office
Hall of Justice, 2nd Floor
1125 3rd Street
Napa, CA 94559

Office: (707) 299-1461

Garrett Veyna
Fire Marshal

MEMORANDUM

9. Roadway radius shall not have an inside radius of less than 50 feet. And additional surface width of 4 feet shall be added to curves of 50-100 feet radius and 2 feet to curves of 100-200 feet radius.
10. **Add to plan: Show hydrant on east side of structure.** Commercial - Approved steamer hydrants shall be installed within 250 feet of any exterior portion of the building as measured along vehicular access roads. Private fire service mains shall be installed, tested and maintained per NFPA 24 2013 edition.
11. Commercial - Fire Department Connections (FDC) for automatic sprinkler systems shall be located fully visible and recognizable from the street or fire apparatus access roads. FDC shall be located within 50 feet of an approved fire hydrant.
12. Commercial - The minimum main size of all fire hydrants shall be 6 inches in diameter. Piping shall be installed with C-900 class 200 piping or ductile iron or equivalent per NFPA 24, 2013 edition for the installation of Underground Fire Protection Mains
13. Commercial - Developments in excess of 10,000 square feet require looped fire mains of a minimum of ten (10) inch diameter to supply fire hydrants spaced at a maximum of 300-foot intervals.
14. An automatic fire sprinkler system shall be installed in accordance with provisions set forth in the California Fire Code as amended by the County of Napa and the applicable National Fire Protection Association Standard. Automatic fire sprinkler systems shall be designed by a fire protection engineer or C-16 licensed contractor.
15. All buildings shall comply with California Fire Code, Chapter 10 Means of Egress requirements. Including but not limited to; exit signs, exit doors, exit hardware and exit illumination.
16. Emergency responder radio coverage **in** new buildings. All new buildings shall have approved radio coverage for emergency responders within the building based upon the existing coverage levels of the public safety communication systems of the jurisdiction at the exterior of the building.

Please note that the comments noted above are based on a Fire Marshal review only. There may be additional comments or information requested from other County Departments or Divisions reviewing this application submittal package. Napa County Fire Marshal's Office Development Guidelines can be found @ www.countyofnapa.org/firemarshal. Should you have any questions of me, contact me at (707)299-1461 or email at garrett.veyna@fire.ca.gov



RECEIVED

JAN 23 2018

Napa County Planning, Building
& Environmental Services

December 1, 2017

John Dobrovich
Rudd Properties, LLC
68 Coombs St., Ste. D-10
Napa, CA 94559

SUBJECT: Request for Water Service "Will-Serve" Letter
Devlin Road Facility
Devlin Road, Napa, CA
(APN's 057-210-037 & -038)

Dear Mr. Dobrovich:

The City of American Canyon has received your request as the Property Owner for a Will-Serve letter for water service to the property located on Devlin Road (Assessor's Parcel Numbers: 057-210-037 and -038; referred to herein as the "Property"). The City is also in receipt of a Use Permit Application (PL17-00274) from the Napa County Planning, Building & Environmental Services Department for the construction of a new mixed-use building totaling approximately 42,708 square feet.

It is the City's understanding that the Property is located within its Extraterritorial Water Service Area¹ and that a Will-Serve Letter for water service to the Property is required prior to the County's approval of a Building Permit. In general, the City reviews the impacts of such requests for service taking into account the overall demand within the its system and known supplies available to meet this demand.

The City's understanding of the current request is based on water demand estimates attached to the Will-Serve Application dated September 21, 2017. At present, the 2.75 acre property is vacant with no historical water demand.

As Table 1 below shows, the requested Average Daily Demand (ADD) is 1,788 gal/day. Table 2 details the requested Maximum Daily Demand (MDD) of 4,090 gal/day for the Property.

¹ As defined by Napa County Local Agency Formation Commission Policy 07-27.

Table 1 – Requested Average Day Demand

<u>Average Daily Water Demand (ADD) in gallons per day:</u>	
Domestic:	485 gpd
Irrigation:	0 ² gpd
Industrial:	1,303 gpd
Total:	1,788 gpd

Table 2 – Requested Maximum Day Demand

<u>Maximum Daily Water Demand (MDD) in gallons per day:</u>	
Domestic:	1290 gpd
Irrigation:	0 gpd
Industrial:	2,800 gpd
Total:	4,090 gpd

The City's Zero Water Footprint (ZWF) Policy requires new development to offset all of its water demands in order to prevent reduction in the reliability of existing water supplies or increases in water rates to existing customers. In light of the information submitted in the Application the City has determined that the Property will not have a Zero Water Footprint because once complete, the Property's proposed ADD (1,788 gpd) will be greater than the established baseline ADD (0 gpd). Because the Owner is requesting service greater than the established baseline demand, the Property will potentially reduce the reliability of existing water supplies and increase costs to existing customers. In accordance with this Policy, because the Property has been determined to not have a Zero Water Footprint, a more detailed Water Supply Report has been prepared, and is attached hereto and made a part of this "Will-Serve" Letter. In order to comply with the ZWF Policy and offset the Property's demand, the applicant shall contribute to the City's ZWF Mitigation Fund whereby the City will continue to undertake water conservation efforts to offset the requested ADD increase of 1,788 gpd. Such efforts will result in this Property achieving a net zero impact to the City's water system, therefore adhering to the ZWF Policy.

This Will-Serve Letter supersedes any other purported service commitments to the Property for any use. By way of this Will-Serve Letter, the City is offering to meet the water service demands shown Tables 1 & 2. The City's offer is

² The project site is located within the Napa Sanitation District's (NSD) recycled water service area. Thus, all irrigation demands will be served with recycled water.

contingent upon the occurrence and/or satisfaction of the following conditions and the continued existence of the following described conditions:

1. Owner shall be subject to all City's rules and regulations, including all fees and charges.
2. At no cost to the City, the Owner shall construct all facilities necessary to serve the Property in accordance with all City standards.
3. Prior to the City's commencement of improvement plan review, the Owner shall submit a deposit in an amount deemed sufficient by the City to fully recover the cost of its plan check and inspection services. Should this initial deposit be insufficient, the Owner agrees to make additional deposits as necessary for the City to complete its review and inspection. Any unused deposit funds will be returned to the Owner after the Notice of Completion is recorded.
4. The City has experienced potential reduction and/or curtailment of its primary sources of water supply during times of drought. When these reductions occur, the City's demands may exceed available supplies. In an effort to reduce this undesirable imbalance, the City is taking steps to reduce customer demands while also seeking to acquire additional supplies. The cost of these additional supplies is unknown at this time, and is not included in the current City water rates. The City is considering implementing potential changes to its rate structure which would be applied in a uniform manner in order to acquire such supplies. The Owner agrees to waive any protest to changes to current City water rates necessary to acquire additional water supplies during their formulation, implementation and review under the California Environmental Quality Act, Public Resources Code section 21000 et seq. ("CEQA") as long as such changes are initiated during the term of this Will Serve Water Supply Agreement or any extension thereof. Moreover, the Owner acknowledges that the City, during dry years, may be unable to meet the Property's water service demands and that its water service may be uniformly reduced and/or curtailed entirely. Owner further agrees to indemnify, defend and hold harmless the City, its elected officials, officers, attorneys, employees or agents for any and all damages or claims of damages stemming from such uniform reductions or curtailments that may occur as long as they are directly related to the City's provision for water to the Property.
5. As a result of *Vineyard Area Citizens for Responsible Growth v. Rancho Cordova* (2007) 40 Cal.4th 412, the County, as lead agency pursuant to CEQA, prior to approval of the Project must, at a minimum during its environmental review:

- a. Present sufficient facts to evaluate the pros and cons of supplying the water that the Project will need; and
 - b. Present analysis that assumes that all phases of the Project will be built and will need water, and includes an analysis to the extent reasonably possible of the consequences of the impacts of providing water to the entire project; and
 - c. Where it is impossible to determine that anticipated future water sources will be available, some discussion of possible replacement sources or alternatives to use of anticipated water and of the environmental consequences of those impacts must be presented.
6. The Owner agrees its financial obligation for water service is as follows:
- a. Monthly water service charges will be billed at the current rate (Outside City Rate, currently \$5.28 per 100 cubic feet) in effect at the time of service and are subject to change. Additionally, a \$2.00/unit drought surcharge, and an estimated meter fee of \$291.49 will be included in monthly service charges.
 - b. The water capacity fee for the Property will be \$86,871.60³ based on a MDD of 4,090 gpd.
 - c. The ZWF Mitigation (offset) cost for the Property is \$16,504.62⁴ in order to achieve compliance with the ZWF Policy. Such mitigation funds are due and payable prior to issuance of a building permit.
7. The Property shall incorporate the following water conservation best management practices:
- Ultra-low-flow toilets in restrooms
 - Waterless urinals (optional)
 - Motion sensor faucets
 - On demand (Instahot) hot water heaters for individual restrooms or the plumbing of hot water return lines with an integral pump if using a centralized tank or tankless unit
 - Installation of an ET Smart irrigation controller
 - Recycled water for landscaping
 - Education of employees regarding water conservation (offered in both English and Spanish)
8. The Property shall not be allowed to use potable water for landscape irrigation purposes. The Property shall install the necessary facilities to utilize recycled water for all landscape irrigation demands.

³ Calculation: 4,090 gpd x \$21.24 = \$86,871.60

⁴ Calculation: 1,788 gpd/65 gpd x \$600 = \$16,504.62

Letter to John Dobrovich
Rudd Properties
December 1, 2017
Page 5

9. The City reserves the right to audit the site's water demand as deemed necessary in order to verify that the Owner's water use is in accordance with this Will-Serve letter.
10. Future changes to the Project with respect to the change in use or water demands shall require that a new Will-Serve Letter be issued.

This Will-Serve Letter will remain valid until October 26, 2019. The City reserves the right to further condition and/or deny the extension of water service if the Project is different from that which presently proposed and authorized or if events out the City's control impact the City's ability to furnish water.

Except to the extent set forth, this letter does not create a liability or responsibility to the Owner or to any third party on behalf of the City. The City does not make a determination as to land use entitlements required for the proposed project, and the issuance of this Will Serve letter shall not be construed to be an expression of the City of a position regarding the use or intensity of use of the development Property or that the County has complied with applicable law in assessing the proposed project under CEQA.

This Will Serve letter becomes effective only upon the express acknowledgement and acceptance of the conditions set forth herein as demonstrated by the execution of the acceptance provision set forth below and the transmittal of the executed acceptance to the City.

Sincerely yours,



Steven L. Hartwig, P.E., T.E.
Interim Public Works Director

cc: Jason Holley, Interim City Manager
William Ross, City Attorney
Sean Trippi, Napa County Planning Department
Susan Presto, Finance Manager
Utility Billing

Letter to John Dobrovich
Rudd Properties
December 1, 2017
Page 6

ACCEPTANCE
of
City's Conditional Offer of Water Service for

Rudd Properties, LLC
Devlin Road Facility

Devlin Road, Napa CA
Napa County Assessor's Parcel Number 057-210-037 & -038

I, Chris Economou, VP Real Estate,
(Print Name) (Print Title)

accept the conditions set forth in this communication.


(Signature)

Date: 12-19-17

CITY OF
AMERICAN
CANYON



RECEIVED

JAN 23 2018

Napa County Planning, Building
& Environmental Services

PUBLIC WORKS DEPARTMENT

4381 BROADWAY, SUITE 201
AMERICAN CANYON, CA 94503

WATER SUPPLY REPORT

FOR

**Rudd Properties, LLC
Devlin Road Facility**

Devlin Road, Napa, CA
Napa County Assessor's Parcel Numbers 057-210-037
& -038

Prepared by:

Clark Stauffer / Mike Beutler
Development Services Engineer

Approved by:



Steven L. Hartwig, P.E., T.E.
Interim Public Works Director

12/21/17

Date

TABLE OF CONTENTS

PREFACE.....2

SECTION 1.0 - REQUEST FOR SERVICE3

SECTION 2.0 - PROJECT WATER FOOTPRINT5

SECTION 3.0 – CAPACITY FEES AND SERVICE CHARGES7

SECTION 4.0 - *VINEYARDS* ANALYSIS8

ACKNOWLEDGEMENT OF WATER SUPPLY ANALYSIS10

PREFACE

This Water Supply Report (WSR) is prepared in response to a request received by the City of American Canyon for a new water service(s) and/or an expansion of existing water service(s). The intent of the WSR is to help inform the discretionary approval process undertaken in conjunction with the request. Chief among its purpose is to:

- Determine if the request is consistent with City ordinances, policies, and practices;
- Determine whether the City's water supply is sufficient to grant the request when compared to existing and other planned future uses, including agricultural and manufacturing uses; and
- To establish a water allocation for the property.

On October 23, 2007, the American Canyon City Council adopted the following definition as the basis for its Zero Water Footprint (ZWF) Policy:

Zero Water Footprint – No loss of water service reliability or increase in water rates to the City of American Canyon's existing water service customers due to requested increase demand for water within the City's water service area.

The overarching intent of the ZWF Policy is to require all new development (residential or non-residential), or the expansion of existing commercial and industrial development, to mitigate all new water demands with "wet-water" offsets by one or more of the following options:

- Reducing existing potable water demands on-site
- Funding programs or constructing projects that would conserve an equivalent amount of water elsewhere within the water service area
- Funding of and/or constructing projects that would increase an equivalent amount of recycled water use elsewhere within the water service area where potable water is currently used.
- Purchase new water supplies from other water providers

SECTION 1.0 - REQUEST FOR SERVICE

1.1 - Property Description

The property is located on Devlin Road (Assessor's Parcel Number: 057-210-037 and - 038) and includes approximately 2.75 acres of undeveloped land; referred to herein as the "Property." The Property is zoned Industrial Park (IP) and is located within the City's Extraterritorial Water Service Area (ETSA) ¹.

1.2 - Project Description

The proposed project is a new mixed use building totaling approximately 42,708 square feet. Entitlements required include a Use Permit from Napa County (PL17-00274) and Will-Serve Letters from the City (for potable water service - domestic and fire service) and Napa Sanitation District (for sewer and recycled water service)².

The project incorporates the following water conservation best management practices:

- Ultra low-flow toilets in restrooms
- Waterless urinals (optional)
- Motion sensor faucets
- On demand (Instahot) hot water heaters for individual restrooms or the plumbing of hot water return lines with an integral pump if using a centralized tank or tankless unit
- Installation of an ET Smart irrigation controller
- Recycled water for landscaping
- Education of employees regarding water conservation (offered in both English and Spanish)

1.3 - Status of Existing Services

The property is currently vacant. The City has no record of historical potable water use at the property. No prior Will-Serve Letters have been issued by the City. The project site is also located within the Napa Sanitation District's (NSD) recycled water service area, thus recycled water will be used for all irrigation demands.

¹ As defined by Napa County Local Agency Formation Commission Policy 07-27.

² The project site is located within the Napa Sanitation District's (NSD) recycled water service area. Recycled water is available to the site and all irrigation demands will be served with recycled water.

1.4 - Will Serve Application

A Will-Serve Application dated July 21, 2017 was submitted on behalf of the Owner, John Dobrovich of Rudd Properties, LLC. The application submitted (see attached) details the anticipated and existing water demands for the project. Staff has reviewed the provided application and finds the estimate to be consistent with industry standards for similar uses.

1.5 - Annualized "Average-Day" Demand (ADD)

As shown on Table 1, based on a 7-day work week for the buildings, the annualized "Average-Day" Demand (ADD) is 1,788 gallons per day.

Table 1 - Property ADD			
Domestic (gpd)	Industrial (gpd)	Irrigation (gpd)	Total (gpd)
485	1,303	0	1,788

1.6 - Maximum Day Demand (MDD)

As shown in Table 2, the anticipated Maximum Demand (MDD) for the Property is 4,090 gpd.

Table 2 - Property MDD			
Domestic (gpd)	Industrial (gpd)	Irrigation (gpd)	Total (gpd)
1290	2,800	0	4,090

SECTION 2.0 - PROJECT WATER FOOTPRINT

2.1 - Project Demand Consistency with UWMP and APMC 13.10

The City's 2010 Urban Water Management Plan (UWMP) assumes industrially zoned property will have up to a maximum ADD of 675 gpd per acre. American Canyon Municipal Code Section 13.10 further limits industrially zoned property within City limits and the broader City ETSA up to a maximum ADD of 650 gpd per acre. As shown in Table 3 below, the Property's estimated ADD (650 gpd per acre) is not more than the maximum allowed by the UWMP and APMC 13.10:

Table 3 - Maximum ADD				
Parcel Size (acres)	UWMP max. allowable ADD (gpd)	APMC 13.10 max. allowable ADD (gpd)	Property ADD (gpd)	Property ADD (gpd/acre)
2.75	1,856	1,788	1,788	650

2.2 - Baseline Water Footprint

The Property's Baseline Water Footprint is determined as one of the following: a) the approved demand amount specific in a current, (unexpired) Will-Serve Letter, Water Supply Report and/or Water Service Agreement; b) the water demand calculated from an audit of three-years of water use; or c) absent other information, the water demand in 2007. As shown in Table 4 below, the Property's baseline water footprint is 0 gpd.

Table 4 - Baseline Water Footprint			
Approved Demand (gpd)	Audited Demand (gpd)	Historical Demand (gpd)	Baseline Water Footprint
N/A	N/A	0	0

2.3 - Zero Water Footprint Determination

Because the Property ADD (1,788 gpd) exceeds the Property's Baseline Water Footprint, the Property does not have a Zero Water Footprint (ZWF). Because the Property does not have a ZWF, the new demand(s) on the City's water system could potentially result in a loss in water service reliability or increase in water rates to the City's existing customers.

2.4 - Demand Offset

The City has an established various programs intended offset new demand(s) on its water system. The Property has agreed to participate in one such program whereby old plumbing fixtures in existing residences (such as toilets, showers and faucets) are replaced with high-efficiency fixtures. On average the cost to replace the fixtures in a single family dwelling unit is \$600 and results in an on-going savings of 65 gpd. By facilitating the replacement of these fixtures city-wide, the Property's new demand is offset by water which is saved elsewhere. The Property has agreed to contribute \$16,504.62³ to the City's Zero Water Footprint Mitigation Fund. Monies in the Fund are used to pay for replacement of plumbing fixtures. The amount paid will result in equivalent savings of 1,788 gpd, thereby offsetting the Property's new ADD.

2.5 - Project Impact on Reliability & Rates

The City's water treatment, delivery and storage system is reliable to serve demands of existing development that existed at the time of ZWF Policy implementation in 2007. New or increased demands to the City's system after the implementation of the ZWF Policy are determined to potentially have a negative impact on the City's water system reliability which could result in an increase in water rates of existing customers. By facilitating the replacement of inefficient plumbing fixtures through the monetary contribution to the City's ZWF Mitigation Fund, the Property has offset its new demand and thus, it is reasonable to conclude that it will have no impact on reliability or rates.

2.6 - Short term mitigations

The water impacts of the Property will be fully mitigated by the financial contribution it has already made to the water capacity fee program in addition to the ZWF Mitigation fee it will make to mitigate 100% of the Property's new water demand.

2.7 - Long term mitigations

The City's Water Shortage Emergency Plan authorizes the City Council to declare a water shortage emergency⁴. Emergencies are declared in four stages with specific reduction methods used for each stage. In the event the

³ Calculation: $1,788 \text{ gpd} / 65 \text{ gpd} \times \$600 = \$16,504.62$

⁴ ACMC §13.14.070

City experiences short term water shortages and determines it is necessary to purchase dry year water the Owner shall provide funds to the City of American Canyon to purchase dry-year water. Upon demand of the Public Works Director, when a water shortage has been declared by the City Council, the project may have to contribute a reasonably determined and reasonably allocated non-refundable payment to the water operations fund to allow the City to acquire dry-year water, if reasonably necessary. The projects contribution shall be equal to the properties reasonably allocated annual demand (AFY) times the City's reasonable cost of a one-year transfer. The annual demand will be implemented uniformly to all City water uses, determined by a City water audit of all City water uses for the previous water year and the analysis in reasonable detail made available to the Owner for reasonable review and comment prior to implementation. The contribution shall be recalculated and made on an annual basis, as reasonably necessary.

SECTION 3.0 – CAPACITY FEES AND SERVICE CHARGES

3.1 - Capacity Fee

Based on the American Canyon Water Capacity Fee Ordinance⁵, the Property shall pay a Water Capacity Fee is \$86,871.60. This amount one-time fee is based on the rate of \$21.24 per gallon x MDD (4,090 gpd).

3.2 – Service Charge

The Property is located outside the City's corporate boundary but within the City's Extraterritorial Water Service Area as defined by LAFCO. Based on the American Canyon Water Capacity Fee Ordinance⁶, the Property shall pay a monthly service charge in the amount of \$5.28/100 cubic feet, plus any drought surcharges and monthly meter fees. Based on the ADD, drought surcharge of \$2.00/unit, and meter fee of \$291.49 per month, the estimated water service charge is approximately \$820 per month.

3.3 - Reimbursable Improvements

The Property proposes no improvement that would be eligible for reimbursement.

⁵ ACMC §13.06.090

⁶ ACMC §13.06.040

SECTION 4.0 - VINEYARDS ANALYSIS

4.1 – Vineyards Decision

The California Supreme Court decision "*Vineyard Area Citizens for Responsible Growth v. City of Rancho Cordova and Sunrise Douglas Property Owners Association, et al.*" sets forth guidelines for evaluating the water supply of a project under the California Environmental Quality Act (CEQA). It requires that water supplies not be illusory or intangible, that water supply over the entire length of the project be evaluated, and that environmental impacts of likely future water sources, as well as alternate sources, be summarized.

4.2 - Facts With Respect to Existing Water Supply and Demand

The City's 2015 Urban Water Management Plan (UWMP) analyzed existing demands and anticipated future demand growth. The 2015 UWMP also quantified the amounts and reliability of its water supplies in various planning horizon scenarios.

The City has entered into enforceable long-term contracts for its supply of potable water. The suppliers are the State Department of Water Resources (DWR) and City of Vallejo. The DWR supplies are provided by the State Water Project (SWP) and they vary each year up to a maximum of 5,200 acre-feet. The Vallejo supplies are 500 acre-feet of raw water as needed and up to 2,640 acre-feet of treated water may be purchased as a retail customer.

City customers consumed 2,976 acre-feet of SWP water in 2015. The 2015 UWMP determined adequate supplies exist for all planning horizons and supply scenarios, except for the "2030 single-dry scenario".

New water demand from the Project and reduced per capita consumption (facilitated by the City's Water Conservation Program) was anticipated as part of the assumed future demand growth in all planning horizons and supply scenarios in the 2015 UWMP. If the total ADD or MDD exceed the totals shown in this report, the applicant will be subject to penalties in-place at the time and has agreed to take the necessary measures to reduce demand to comply with this report.

4.3 – Anticipated Water Supplies over the Life of the Project

The City has developed a capacity fee capital program and water conservation program which, when implemented, will reasonably ensure an

adequate supply of potable water and recycled water to meet demands under normal years, multiple-dry-years, and single-dry-years.

By fully complying with the City's ZWF Policy, the project will offset its new demand by paying an in-lieu fee that will be used by the City to implement its water conservation efforts to reduce potable water demands throughout its Water Service Area. Given the City's efforts to expand its water portfolio in terms of supply, storage, and conservation, and the fact that this project will not result in an increased demand on the existing system, it is reasonable to project there is sufficient water supply over the life of the project.

4.4 – Environmental Impacts of Likely Future Water Sources

According to the 2015 UWMP, adequate long-term supplies exist for all planning horizons and supply scenarios, except for the "2030 single-dry scenario". The Project will offset its new demand by paying an ZWF Mitigation fee that will be used by the City to further its water conservation efforts to reduce potable water demands throughout its Water Service Area. These efforts will have no significant impacts to the physical environment.

Moreover, it is unlikely that additional long-term supplies will need to be developed to meet the new demands attributable to the Project and it would be unnecessarily speculative to analyze the potential impact of such an unlikely activity.

Lastly, the City Council adopted a Mitigated Negative Declaration in November 2003 in conjunction with the adoption of the Recycled Water Facilities Plan. That plan identifies a series of projects which in conjunction with the water conservation program will reduce potable water demands throughout its Water Service Area. Impacts caused by implementation Recycled Water Facilities Plan are less than significant because the new recycled water distribution pipelines were to be located in existing paved public rights of way.

ACKNOWLEDGEMENT OF WATER SUPPLY ANALYSIS

**Rudd Properties, LLC
Devlin Road Facility**

**Devlin Road, Napa, CA
Napa County Assessor's Parcel Numbers 057-210-037 & -038**

I, Chris Economou, VP Real Estate,
(Print Name) (Print Title)

acknowledge and accept the water supply analysis as set forth in this Water
Supply Report dated _____, 2017.


(Signature)

Date: 12-19-17



August 1, 2017

Conservation, Development and Planning Department – County of Napa
1195 Third Street, Room 210
Napa, CA 94559

SUBJECT: APN 057-210-037 & 057-210-038 – Sheehy Building
NSD Will Serve #065

To Whom It May Concern:

The Napa Sanitation District has received a request to provide a "Will Serve" letter for a proposed 42,708 SF building located on the subject parcels. The subject parcels are currently within the District's Sphere of Influence and within the District's boundaries. The District will provide sanitary sewer and recycled water service to these parcels.

The following items will be required by the owner/developer:

1. Install the sanitary sewer and recycled water improvements as specified in the District's Conditions of Approval for the project upon submission of an application.
2. Pay the appropriate capacity and development fees. The facility shall be subject to all applicable rules and regulations of the District.
3. Enter into an Industrial User permit for industrial process wastewater discharged to the District and/or sign a zero-waste discharge permit for process wastewater that is held onsite and hauled to an approved disposal site (if applicable).

The District has been informed that the proposed building addition will generate approximately 2,722 gallons of domestic wastewater per day which is equivalent to the flow of approximately 13 single-family dwelling.

This parcel is within the District's Recycled Water Benefit Zone. The development will be required to install the necessary facilities to utilize recycled water for landscape irrigation, when it becomes available to the property in the future. The project has requested service to approximately 0.29 acres of landscaping, with a recycled water demand of approximately 0.77 acre-feet per year. The District will provide recycled water service to this parcel.

This "Will Serve" letter for sanitary sewer and recycled water service is valid for a period of three (3) years from the date of this letter. If the proposed

NapaSan
1515 Soscol Ferry Road
Napa, CA 94558

Office (707) 258-6000
Fax (707) 258-6048

www.napasand.com


development has not obtained its required Connection Permits from the District at the end of this time, this "Will Serve" letter shall become void. If you have any questions regarding this matter, please contact me at (707) 258-6031 or rgamble@napasan.com.

Sincerely,

Robin D. Gamble Holley

Robin Gamble Holley
Asset Manager

cc: Alan Spence



NapaSan

COLLECTION • TREATMENT • RECOVERY • REUSE

August 17, 2017

Conservation, Development, and Planning
County of Napa
1195 Third Street, Suite 210
Napa, CA 94559

SUBJECT: 17-274 SHEEHY BUILDING, REFRL-000772, RSA+, (Trippi)

The Napa Sanitation District has reviewed the above-named application. The following are the conditions of approval for the project.

The owner shall pay to the District the prevailing fees and charges in effect as established by Resolutions and Ordinances before the issuance of a County Building Permit, and shall adhere to the rules and regulations as they apply to the application.

The District has identified the following comments based on the current application. The District reserves the right to modify the following conditions/comments based on changes to future applications or changes to the project site plan. The proposed project shall be subject to the following conditions of approval:

1. A plan showing the required sanitary sewer improvements shall be prepared by a registered civil engineer conforming to NapaSan standards, and shall be submitted to NapaSan for approval.
2. The subject parcel shall use recycled water for their landscape irrigation.
3. Discharge lines from the elevator sump pits shall not be connected to the sanitary sewer system.
4. No floor drains are allowed in the building except in the restroom and food service areas.
5. No plumbing from the outdoor pool/spa areas or water features shall be connected to the sanitary sewer system.
6. A grease interceptor will be required for any restaurant or food service type of uses.
7. The drain in the trash enclosure shall be connected to a grease interceptor and the trash enclosure shall meet the NapaSan standards. Contact NapaSan for more information.
8. If the applicant desires to discharge the process wastewater to NapaSan in the future or if NapaSan determines the future use is an industrial use, the owner would be required to pay capacity charges to NapaSan based on the rates in effect at the time and would be subject to the

rules and regulations in effect at that time. At a minimum the facility would be subject to the following:

- a. Installation of a flow meter and sampler on the process waste line
 - b. Ensure that the discharge conforms with NapaSan's Local Limits
 - c. Provide NapaSan with a wastewater treatment plan
 - d. Obtain an Industrial Waste Discharge Permit from NapaSan for the operation. Permit conditions would be established by NapaSan at the time an application is made by the owner.
9. If the applicant desires the industrial waste to be handled by a hold and haul method and no discharge to NapaSan's sanitary sewer facilities will occur, documentation of who will be hauling the waste shall be provided to NapaSan and the applicant shall enter into a zero-waste discharge permit with NapaSan.
10. NapaSan has Best Management Practices (BMPs) for specific industries/businesses which contain proven practices for reducing pollution in wastewater. Some BMPs are mandatory. The proposed project shall comply with mandatory BMPs. All sewer discharges from the proposed development shall the Local Limits for constituents of concern established by NapaSan.
11. The proposed development would be subject to the following fees, based on the rates in effect at the time they are paid:
- a. Plan Check Fees
 - b. Inspection Fees
 - c. Capacity Charges (based on use and square footage for commercial. Outdoor dining and event space is included in the square footage)
 - d. Capacity Charges (for the domestic waste stream shall be based on fixture units per Section 5.02.030.B of District Code. The capacity charges for the process waste stream shall be calculated per Section 5.02.030.B of District Code. The owner shall contact the NapaSan for additional information).
12. NapaSan has updated sanitary sewer and recycled water standard specifications and details. The updated specifications and details are available online at NapaSan's website (www.NapaSan.com). NapaSan may revise the standard specifications and details at any time. It is the responsibility of the engineer, contractor, and developer to verify that they are in possession of the current version of the standards prior to design and construction of sanitary sewer and recycled water improvements.

The capacity charge for an equivalent dwelling unit currently is \$9,299 and will increase by the Consumer Price Index (CPI) annually in July. Commercial capacity charges are determined per NapaSan Code Section 5.02.030.B. Contact NapaSan Staff for additional information regarding capacity charges.

Please include this information as a part of your consideration of the application.

Sincerely,

Robin D. Gamble Holley

Robin Gamble Holley
Asset Manager