

“B”

**Recommended Conditions of Approval
and Final Agency Approval Memos**

**ZONING ADMINISTRATOR HEARING – MARCH 24, 2021
RECOMMENDED CONDITIONS OF APPROVAL**

**SEBASTIEN MARINEAU-MES RESIDENCE VIEWSHED
Application Number P20-00230-VIEW
4000 Silverado Trail N., Calistoga, California
APN #021-010-077**

This Permit encompasses and shall be limited to the project commonly known as the Sebastien Marineau-Mes Residence, located at 4000 Silverado Trail, N. Part I encompasses the Project Scope and general conditions pertaining to statutory and local code references, project monitoring and the process for any future changes or activities. Part II encompasses the ongoing conditions relevant to the operation of the project. Part III encompasses the conditions relevant to construction and the prerequisites for a Final Certificate of Occupancy. It is the responsibility of the permittee to communicate the requirements of these conditions and mitigations (if any) to all designers, contractors, employees, and the general public to ensure compliance is achieved.

Where conditions are not applicable or relevant to this project, they shall be noted as “Reserved” and, therefore, have been removed.

When modifying a legally established entitlement related to this project, these conditions are not intended to be retroactive or to have any effect on existing vested rights except where specifically indicated.

PART I

1.0 PROJECT SCOPE

This Permit encompasses and shall be limited to:

- 1.1 Approval of a Viewshed Application to allow the construction of a new 3,996 sq. ft. single-family residence, 1,125 sq. ft. garage, 972 sq. ft. accessory dwelling unit over the garage, swimming pool; driveway improvements to County Road and Street Standards; construction of a ±5,000 gallon water storage tank; installation of wastewater treatment system; and, associated infrastructure consistent with the Napa County Code.

The residence and associated improvements shall be designed in substantial conformance with the submitted site plan, elevation drawings, and other submittal materials and shall comply with all requirements of the Napa County Code (County Code). It is the responsibility of the permittee to communicate the requirements of these conditions and mitigations (if any) to all designers, contractors, employees, and the general public to ensure compliance is achieved. Any expansion of or change in use or alternative locations for fire suppression or other types of water tanks shall be approved in accordance with the County Code and may be subject to the permit modification process.

2.0 STATUTORY AND CODE SECTION REFERENCES

All references to statutes and code sections shall refer to their successor as those sections or statutes may be subsequently amended from time to time.

3.0 MONITORING COSTS

All Staff costs associated with monitoring compliance with these conditions, previous permit conditions, and project revisions shall be borne by the permittee and/or property owner. Costs associated with conditions of approval and mitigation measures that require monitoring, including investigation of complaints, other than those costs related to investigation of complaints of non-compliance that are determined to be unfounded, shall be charged to the property owner or permittee. Costs shall be as established by resolution of the Board of Supervisors in accordance with the hourly consulting rate established at the time of the monitoring and shall include maintenance of a \$500 deposit for construction compliance monitoring that shall be retained until issuance of a Final Certificate of Occupancy. Violations of conditions of approval or mitigation measures caused by the permittee's contractors, employees, and/or guests are the responsibility of the permittee.

The Planning Commission may implement an audit program if compliance deficiencies are noted. If evidence of a compliance deficiency is found to exist by the Planning Commission at some time in the future, the Planning Commission may institute the program at the permittee's expense (including requiring a deposit of funds in an amount determined by the Commission) as needed until compliance assurance is achieved. The Planning Commission may also use the data, if so warranted, to commence revocation proceedings in accordance with the County Code.

PART II

4.0 OPERATIONAL CHARACTERISTICS OF THE PROJECT [RESERVED]

PART III

5.0 PREREQUISITE FOR ISSUANCE OF PERMITS

5.1 PAYMENT OF FEES

No building, grading or sewage disposal permits shall be issued or other permits authorized until all accrued planning permit processing fees have been paid in full. This includes all fees associated with plan check and building inspections, associated development impact fees established by County Ordinance or Resolution, and the Napa County Affordable Housing Mitigation Fee in accordance with County Code.

6.0 GRADING/DEMOLITION/ENVIRONMENTAL/BUILDING PERMIT/OTHER PERMIT PREREQUISITES

Permittee shall comply with the following with the submittal of a grading, demolition environmental, building and/or other applicable permit applications:

6.1 COMPLIANCE WITH OTHER DEPARTMENTS AND AGENCIES - PLAN REVIEW, CONSTRUCTION AND PREOCCUPANCY CONDITIONS

The project conditions of approval include all of the following County Divisions, Departments and Agencies' requirements. The permittee shall comply with all applicable building codes, zoning standards, and requirements of County Divisions, Departments and Agencies at the time of submittal and may be subject to change.

- a. Engineering Services Division review/construction/preoccupancy conditions as stated in their Memorandum dated January 6, 2021.
- b. Fire Department review/construction/preoccupancy conditions as stated in their Memorandum dated October 6, 2020.

The determination as to whether or not the permittee has substantially complied with the requirements of other County Divisions, Departments and Agencies shall be determined by those County Divisions, Departments or Agencies. The inability to substantially comply with the requirements of other County Divisions, Departments and Agencies may result in the need to modify the permit.

6.2 BUILDING DIVISION – GENERAL CONDITIONS

Please contact the Building Division with any questions regarding the following:

- a. A building permit shall be obtained for all construction occurring on the site not otherwise exempt by the CBC or any State or local amendment adopted thereto.
- b. If there are any existing structures and/or buildings on the property that will need to be removed to accommodate construction activities, a separate demolition permit shall be required from the Building Division prior to removal. The permittee shall provide a “J” number from the Bay Area Air Quality Management District (BAAQMD) at the time the permittee applies for a demolition permit if applicable.
- c. All areas of newly designed and newly constructed buildings, facilities and or site improvements shall comply with the CBC accessibility requirements, as well as, American with Disabilities Act requirements when applicable. When alterations or additions are made to existing buildings or facilities, an accessible path of travel to the specific area of alteration or addition shall be provided, as required per the CBC.

6.3 LIGHTING – PLAN SUBMITTAL

- a. Two (2) copies of a detailed lighting plan showing the location and specifications for all lighting fixtures to be installed on the property shall be submitted for Planning Division review and approval. All lighting shall comply with the CBC.
- b. All exterior lighting, including landscape lighting, shall be shielded and directed downward; located as low to the ground as possible; the minimum necessary for security, safety, or operations; on timers; and shall incorporate the use of motion detection sensors to the greatest extent practical. All lighting shall be shielded or placed such that it does not shine directly on adjacent properties or impact vehicles on adjacent streets. No flood-lighting or sodium lighting of the building is permitted, including architectural highlighting and spotting. Low-level lighting shall be utilized in parking areas as opposed to elevated high-intensity light standards.

6.4 LANDSCAPING – PLAN SUBMITTAL

- a. Two (2) copies of a detailed final landscaping and irrigation plan, including parking details, shall be submitted with the building permit application package for the Planning Division’s review and approval prior to the issuance of any building permit associated with this permit. The plan shall be prepared pursuant to the Water Efficient Landscape Ordinance (Chapter 18.118 of the County Code) requirements in effect at the time of building permit application submittal, as applicable, and shall indicate the names and locations of all plant materials to be used along with their method of maintenance.
- b. Plant materials shall be purchased locally when practical, and, to the greatest extent possible, the plant materials shall be the same native plants found in Napa County. The Agricultural Commissioner’s office shall be notified of all impending deliveries of live plants with points of origin outside of Napa County.
- c. No trees greater than 6” diameter at breast height shall be removed, except for those identified on the submitted site plan. Trees to be retained shall be protected during construction by fencing securely installed at the outer most dripline of the tree or trees. Such fencing shall be maintained throughout the duration of the work undertaken in connection with development/construction. In no case shall construction material, debris or vehicles be stored in the fenced tree protection area.

6.5 COLORS

Exterior finishes and colors of the building, roof, parking lot and walkways shall be subject to approval by the Planning Division in conjunction with building permit review and/or prior to painting. Highly reflective surfaces are prohibited.

6.6 OUTDOOR STORAGE/SCREENING/UTILITIES **[RESERVED]**

6.7 MECHANICAL EQUIPMENT **[RESERVED]**

6.8 TRASH ENCLOSURES **[RESERVED]**

6.9 ADDRESSING

All project site addresses shall be determined by the PBES Director, and be reviewed and approved by the United States Post Office. The PBES Director reserves the right to issue or re-issue an appropriate situs address at the time of issuance of any building permit to ensure proper identification and sequencing of numbers. For multi-tenant or multiple structure projects, this includes building permits for later building modifications or tenant improvements.

6.10 HISTORIC RESOURCES **[RESERVED]**

6.11 DEMOLITION ACTIVITIES

All demolition activities associated with the single family and agricultural out-buildings shall be completed, landscaping installed, and debris cleared from the subject parcel.

6.12 VIEWSHED – EXECUTION OF USE RESTRICTION

The property owner shall execute and record in the county recorder’s office a use restriction, in a form approved by County Counsel, requiring that building exteriors, existing and proposed covering vegetation, as well as any equivalent level of replacement vegetation to be maintained by the owner or the owner’s successor so as to maintain conformance with the County Code.

6.13 PERMIT PREREQUISITE MITIGATION MEASURES

a. Biological Resources

MM BIO-1. Tree removal shall be performed from September 1 through March 31, outside of the general bat maternity season. If tree removal is proposed during this period, it is recommended that a bat habitat assessment and survey effort (the latter if needed) be performed by a qualified biologist prior to tree removal to determine if bats are present in the trees. If no suitable roosting habitat for bats is found, then no further study is warranted. If special-status bat species or bat maternity roosts are detected, then roost trees shall be avoided until the end of the maternity roosting season as determined by a qualified biologist in consultation with CDFW. Irrespective of time of year, all felled trees should remain on the ground for at least 24 hours prior to chipping, off-site removal, or other processing to allow any bats present within the felled trees to escape.

Method of Monitoring: The permittee shall have a bat habitat assessment and survey, as applicable, prior to any tree removal during the bat maternity season (April 1 to August 31). In the event special-status bat species or bat maternity roosts are detected, construction activities will be scheduled to avoid the maternity roosting season.

MM BIO-2 Tree/vegetation removal and initial ground disturbance shall occur from August 16 to January 31, outside of the general bird nesting season. If tree/vegetation is proposed during this time, a pre-construction nesting bird survey shall be performed by a qualified biologist no more than 14 days prior to the initiation of tree removal or ground disturbance. The survey should cover the Project Area (including tree removal areas) and surrounding areas within 500 feet. If active bird nests are found during the survey, an appropriate no-disturbance buffer shall be established by the qualified biologist. Once it is determined that the young have fledged (left the nest) or the nest otherwise becomes inactive (e.g., due to predation), the buffer may be lifted and work may be initiated within the buffer.

Method of Monitoring: The permittee shall have a nesting bird survey completed prior to any ground disturbing activities scheduled to occur on the site from February 1 through August 15. The survey results shall be provided to the Napa County Planning, Building and Environmental Services. In the event any special-status or other protected nesting birds are found to occur on-site construction activities shall be scheduled to avoid nesting and breeding periods and consultation will be sought with CDFW to develop appropriate measures to reduce potential impacts to nesting birds protected under the Migratory Bird Treaty Act.

6.14 PARCEL CHANGE REQUIREMENTS **[RESERVED]**

6.15 FINAL MAPS **[RESERVED]**

6.16 OTHER CONDITIONS APPLICABLE TO THE PROJECT PERMITTING PROCESS

- b. The property owner shall execute and record in the county recorder's office, in a form approved by County Counsel, a perpetual protective easement or perpetual deed restriction preserving and conserving the preserved vegetation canopy cover Pursuant to Napa County Code Section 18.108.020(E). The perpetual protective easement or perpetual deed restriction may be combined with the Viewshed Use Restriction and shall be recorded prior to the issuance of building permits.
- c. Additional trees shall be planted to replace those trees lost in the fires as necessary to meet screening requirements.

7.0 PROJECT CONSTRUCTION

Permittee shall comply with the following during project construction:

7.1 SITE IMPROVEMENT

Please contact Engineering Services with any questions regarding the following:

- a. **GRADING & SPOILS**
All grading and spoils generated by construction of the project facilities shall be managed per Engineering Services direction. Alternative locations for spoils are permitted, subject to review and approval by the PBES Director, when such alternative locations do not change the overall concept, and do not conflict with any environmental mitigation measures or conditions of approval.
- b. **DUST CONTROL**
Water and/or dust palliatives shall be applied in sufficient quantities during grading and other ground disturbing activities on-site to minimize the amount of dust produced. Outdoor construction activities shall not occur when average wind speeds exceed 20 mph.

c. AIR QUALITY

During all construction activities the permittee shall comply with the most current version of BAAQMD Basic Construction Best Management Practices including but not limited to the following, as applicable:

1. Post a publicly visible sign with the telephone number and person to contact at the lead agency regarding dust complaints. The BAAQMD's phone number shall also be visible.
2. Water all exposed surfaces (e.g., parking areas, staging areas, soil piles, grading areas, and unpaved access roads) two times per day.
3. Cover all haul trucks transporting soil, sand, or other loose material off-site.
4. Remove all visible mud or dirt tracked onto adjacent public roads by using wet power vacuum street sweepers at least once per day. The use of dry power sweeping is prohibited.
5. All vehicle speeds on unpaved roads shall be limited to 15 mph.
6. All roadways, driveways, and sidewalks to be paved shall be completed as soon as possible. Building pads shall be laid as soon as possible after grading unless seeding or soil binders are used.
7. Idling times shall be minimized either by shutting off equipment when not in use or reducing the maximum idling time to five (5) minutes (as required State Regulations). Clear signage shall be provided for construction workers at all access points.
8. All construction equipment shall be maintained and properly tuned in accordance with manufacturer's specifications. All equipment shall be checked by a certified visible emissions evaluator. Any portable engines greater than 50 horsepower or associated equipment operated within the BAAQMD's jurisdiction shall have either a California Air Resources Board (ARB) registration Portable Equipment Registration Program (PERP) or a BAAQMD permit. For general information regarding the certified visible emissions evaluator or the registration program, visit the ARB FAQ http://www.arb.ca.gov/portable/perp/perpfaq_04-16-15.pdf or the PERP website <http://www.arb.ca.gov/portable/portable.htm>.

d. STORM WATER CONTROL

The permittee shall comply with all construction and post-construction storm water pollution prevention protocols as required by the County Engineering Services Division, and the State Regional Water Quality Control Board.

7.2 ARCHEOLOGICAL FINDING

In the event that archeological artifacts or human remains are discovered during construction, work shall cease in a 50-foot radius surrounding the area of discovery. The permittee shall contact the PBES Department for further guidance, which will likely include the requirement for the permittee to hire a qualified professional to analyze the artifacts encountered and to determine if additional measures are required.

If human remains are encountered during project development, all work in the vicinity must be halted, and the Napa County Coroner informed, so that the Coroner can determine if an investigation of the cause of death is required, and if the remains are of Native American origin. If the remains are of Native American origin, the permittee shall comply with the requirements of Public Resources Code Section 5097.98.

7.3 CONSTRUCTION NOISE

Construction noise shall be minimized to the greatest extent practical and feasible under State and local safety laws, consistent with construction noise levels permitted by the General Plan Community Character Element and the County Noise Ordinance. Construction equipment muffling and hours of operation shall be in compliance with the County Code. Equipment shall be shut down when not in use. Construction equipment shall be staged, loaded, and unloaded on the project site, if at all practicable. If project terrain or access road conditions require construction equipment to be staged, loaded, or unloaded off the project site (such as on a neighboring road or at the base of a hill), such activities only shall occur daily between the hours of 8:00 AM to 5:00 PM.

7.4 OTHER CONSTRUCTION CONDITIONS APPLICABLE TO THE PROJECT PROPOSAL **[RESERVED]**

7.5 CONSTRUCTION MITIGATION MEASURES

a. Biological Resources

MM BIO-1. Tree removal shall be performed from September 1 through March 31, outside of the general bat maternity season. If tree removal is proposed during this period, it is recommended that a bat habitat assessment and survey effort (the latter if needed) be performed by a qualified biologist prior to tree removal to determine if bats are present in the trees. If no suitable roosting habitat for bats is found, then no further study is warranted. If special-status bat species or bat maternity roosts are detected, then roost trees shall be avoided until the end of the maternity roosting season as determined by a qualified biologist in consultation with CDFW. Irrespective of time of year, all felled trees should remain on the ground for at least 24 hours prior to chipping, off-site removal, or other processing to allow any bats present within the felled trees to escape.

Method of Monitoring: The permittee shall have a bat habitat assessment and survey, as applicable, prior to any tree removal during the bat maternity season (April 1 to August 31). In the event special-status bat species or bat maternity roosts are detected, construction activities will be scheduled to avoid the maternity roosting season.

MM BIO-2 Tree/vegetation removal and initial ground disturbance shall occur from August 16 to January 31, outside of the general bird nesting season. If tree/vegetation is proposed during this time, a pre-construction nesting bird survey shall be performed by a qualified biologist no more than 14 days prior to the initiation of tree removal or ground disturbance. The survey should cover the Project Area (including tree removal areas) and surrounding areas within 500 feet. If active bird nests are found during the survey, an appropriate no-disturbance buffer shall be established by the qualified biologist. Once it is determined that the young have fledged (left the nest) or the nest otherwise becomes inactive (e.g., due to predation), the buffer may be lifted and work may be initiated within the buffer.

Method of Monitoring: The permittee shall have a nesting bird survey completed prior to any ground disturbing activities scheduled to occur on the site from February 1 through August 15. The survey results shall be provided to the Napa County Planning, Building and Environmental Services. In the event any special-status or other protected nesting birds are found to occur on-site construction activities shall be scheduled to avoid nesting and breeding periods and consultation will be sought with CDFW to develop appropriate measures to reduce potential impacts to nesting birds protected under the Migratory Bird Treaty Act.

8.0 TEMPORARY CERTIFICATE OF OCCUPANCY – PREREQUISITES [RESERVED]

9.0 FINAL CERTIFICATE OF OCCUPANCY – PREREQUISITES

Permittee shall comply with the following before a Final Certificate of Occupancy is granted by the County Building Official, which upon granting, authorizes all use permit activities to commence:

9.1 FINAL OCCUPANCY

All project improvements, including compliance with applicable codes, conditions, and requirements of all Departments and Agencies with jurisdiction over the project, shall be completed.

9.2 SIGNS [RESERVED]

- 9.3 **GATE/ENTRY STRUCTURES**
Any gate installed at the project entrance shall be reviewed by the PBES Department and the Fire Department to assure that the design allows large vehicles, such as motorhomes, to turn around if the gate is closed without backing into the public roadway, and that fire suppression access is available at all times. If the gate is part of an entry structure an additional permit shall be required pursuant to the County Code and in accordance with the Napa County Roads and Street Standards. A separate entry structure permit is not required if the entry structure is consistent with entry structure plans submitted, reviewed, and approved as part of this permit approval.
- 9.4 **LANDSCAPING**
Landscaping shall be installed in accordance with the approved landscape plan.
- 9.5 **ROAD OR TRAFFIC IMPROVEMENT [RESERVED]**
- 9.6 **DEMOLITION ACTIVITIES [RESERVED]**
- 9.7 **GRADING SPOILS**
All spoils piles shall be removed in accordance with the approved grading permit and/or building permit.
- 9.8 **MITIGATION MEASURES APPLICABLE PRIOR TO ISSUANCE OF A FINAL CERTIFICATE OF OCCUPANCY [RESERVED]**
- 9.9 **OTHER CONDITIONS APPLICABLE PRIOR TO ISSUANCE OF A FINAL CERTIFICATE OF OCCUPANCY [RESERVED]**



A Tradition of Stewardship
A Commitment to Service

Planning, Building & Environmental Services

1195 Third Street, Suite 210
Napa, CA 94559
www.countyofnapa.org

David Morrison
Director

MEMORANDUM

To: Wynpress Balcher Planning Division	From: Alexei Belov Engineering Division
Date: January 6, 2021	Re: 4000 Silverado Trail North – Residence, Auto Court w/Garage & Guest Unit, Pool and Driveway. Engineering COA P20-00230 APN: 030-210-010-000

The Engineering Division received a referral for comment on an administrative viewshed permit. Based upon the information provided in the application, Engineering finds the application **complete** and recommends the following conditions of approval:

RECOMMENDED APPROVAL CONDITIONS:

PREREQUISITES FOR ISSUANCE OF PERMITS

1. Any roadway, access driveway, and parking areas, proposed new or reconstructed shall meet the requirements as outlined in the latest edition of the Napa County Road & Street Standards for Residential development at the time of use permit approval. The property owner shall obtain a grading permit for the proposed roadway and site development improvements.
2. Any improvements constructed within the Public Right-of Way will require an Encroachment Permit from the Department of Public Works.
3. All on site civil improvements including but not limited to the excavation, fill, general grading, drainage, curb, gutter, surface drainage, storm drainage, and parking and driveways, shall be constructed according to plans prepared by a registered civil engineer, which will be reviewed and approved by the Engineering Division of the Napa County Planning, Building and Environmental Services Department (PBES) **prior to the commencement** of any on site land preparation or construction. Plans shall be wet signed and submitted with the building and/or grading permit documents at the time of permit application. A plan check fee will apply.

4. Grading and drainage improvements shall be constructed according to the current Napa County Road and Street Standards, Chapter 16.28 of the Napa County Code, and Appendix J of the California Building Code.
5. **Prior to issuance of a development permit** (i.e. building permit and/or grading permit) the owner shall submit the necessary documents for Erosion Control as determined by the area of disturbance of the proposed development in accordance with the Napa Countywide Stormwater Pollution Prevention Program Erosion and Sediment Control Plan Guidance document, dated December 2014.
6. **Prior to issuance of a development permit** the owner shall prepare a Single Family Dwelling Stormwater Control Plan (SCP) in accordance with the latest edition of the BASMAA Post-Construction Manual for review and approval by the Engineering Division in PBES.

PREREQUISITES FOR FINAL CERTIFICATION OF OCCUPANCY

7. Site shall be completely stabilized to the satisfaction of the County Engineer prior to Final Occupancy.
8. All roadway improvements shall be completed prior to Final Occupancy.

Any changes in use may necessitate additional conditions of approval.

Any changes in use or design may necessitate additional review and approval. If you have any questions regarding the above items please contact Alexei Belov from Napa County PBES Department Engineering Division at (707) 299.2177 or via e-mail at Alexei.Belov@countyofnapa.org.



A Tradition of Stewardship
A Commitment to Service

Napa County Fire Department
Fire Marshal's Office
Hall of Justice, 2nd Floor
1125 3rd Street
Napa, CA 94559

Office: (707) 299-1466

Adam Mone
Fire Plans Examiner

MEMORANDUM

TO: Planning	DATE: 10/6/2020
FROM: Adam Mone, Plans Examiner	
SUBJECT: P20-00239 Sebastien Marineau-Mes	APN: 021-010-077-000

The Napa County Fire Marshal's Office has reviewed the submittal package for the above proposed project. The Fire Marshal approves the project as submitted with the following conditions of approval:

1. All construction and use of the facility shall comply with all applicable standards, regulations, codes and ordinances at time of Building Permit issuance.
2. Beneficial occupancy will not be granted until all fire department fire and life safety items have been installed, tested and finalized.
3. Projects shall have an approved water supply for fire protection be made available as soon as combustible material arrives on the site. All underground fire lines, pump and tank plans are required to be a separate submittal from the building or civil plans.
4. Separate submittals required for Underground Fire Lines, Fire Pump, Automatic Fire Sprinklers
5. All buildings, facilities, and developments shall be accessible to fire department apparatus by way of approved access roadways and/or driveways. The fire access road shall comply with the requirements of the Napa County Road & Street Standards.
6. Access roads shall be designed and maintained to support the imposed loads of fire apparatus and shall be surfaced so as to provide all-weather driving capabilities. Provide an engineered analysis of the proposed roadway noting its ability to support apparatus weighing 75,000 lbs.
7. Provide fire department access roads to within 150 feet of any exterior portion of the buildings as measured by an approved route around the exterior of the building or facility.



A Tradition of Stewardship
A Commitment to Service

Napa County Fire Department
Fire Marshal's Office
Hall of Justice, 2nd Floor
1125 3rd Street
Napa, CA 94559

Office: (707) 299-1466

Adam Mone
Fire Plans Examiner

MEMORANDUM

8. Roadways shall be a minimum of 20 feet in width with a 2 foot shoulder and 15 foot vertical clearance.
9. Driveways shall be a minimum of 10 feet in width with a 4 foot shoulder and 15 foot vertical clearance.
10. Turnouts shall be a minimum of 12 feet in width, 30 foot in length and 25 foot taper on each end.
11. Turnarounds are required on driveways and dead end roadways.
12. Grades for all roadways and driveways shall not exceed 16 percent.
13. Roadway radius shall not have an inside radius of less than 50 feet. And additional surface width of 4 feet shall be added to curves of 50-100 feet radius and 2 feet to curves of 100-200 feet radius.
14. Gates for driveways and/or roadways shall comply with the California Fire Code, section 503.5 and the Napa County Road & Street Standards and CA Fire Safe Regulations for projects within SRA.
15. Provide 100 feet of defensible space around all structures.
16. Provide 10 feet of defensible space fire hazard reduction on both sides of all roadways of the facility.

Please note that the comments noted above are based on a Fire Marshal review only. There may be additional comments or information requested from other County Departments or Divisions reviewing this application submittal package. Napa County Fire Marshal's Office Development Guidelines can be found @ www.countyofnapa.org/firemarshal. Should you have any questions of me, contact me at (707)299-1466 or email at adam.mone@countyofnapa.org