

NAPA COUNTY LAND USE PLAN 1998 - 2000





LEGEND

URBAN TRANSPORTATION LIMITED ACCESS HIGHWAY **CITIES MAJOR ROAD** URBAN RESIDENTIAL SECONDARY ROAD RURAL RESIDENTIAL **RAILROAD COMMERCIAL AIRPORT INDUSTRIAL** F LANDFILL SITE PUBLIC - INSTITUTIONAL **OPEN SPACE** AGRICULTURE, WATERSHED & **OPEN SPACE** SCALE IN MILES AGRICULTURAL RESOURCE APN 027-310-031,32,36,38 04-28-2008













Detail of Parcel 031 Area






Detail of Parcel 032 Area







Vegetation Plan of Parcel 031 Area






Vegetation Plan of Parcel 032 Area








Existing Condition - Proposed Entrance area on Dry Creek Road





Proposed Entrance on Dry Creek Road














WINTERIZING OF DRIVEWAY &EXPOSED EARTH AREAS

TEMPORARY INTERIM EROSION CONTROL MEASURES

BEGIN UPON RECEIVING PERMIT(JUNE 200±). END UPON COMPLETING CONSTRUCTION OF 3. ALL PROJECT PHASES.

CUT AND FILL AREAS AND ALL EXPOSED EARTH SURFACES. THIS WORK SHALL BEGIN UPON STARTING CONSTRUCTION TO CONTAIN SOIL ON THE SITE DURING CONSTRUCTION PER

SPREAD STRAW MULCH OVER ALL EXPOSED EARTH SURFACES WHEN CHANCE OF RAIN IS OVER 70% AS DETERMINED BY THE NATIONAL WEATHER BUREAU, PER APPLICATION SCHEDULE ON SHEET


- INSTALL SILT FENCES BELOW ALL CUT
 AND FILL AREAS AND ALL EXPOSED AND FILL AREAS AND ALL EAFVEST
 EARTH SUFFACES. THIS WORK SHALL
 BEGIN UPON STARTING CONSTRUCTION
 TO CONTAIN SOIL ON THE SITE DURING
 CONSTRUCTION PER PLANS.
- SPREAD STRAW MULCH OVER ALL EXPOSED EARTH SURFACES WHEN
 CHANCE OF RAIN IS OVER 70% AS
 DETERMINED BY THE NATIONAL WEATHER BUREAU, PER APPLICATION SCHEDULE ON SHEET 18.
- 3. INSTALL WATER BARS AND CHECK DAMS PER PLAN IN THE EVENT PERMANENT EROSION MEASURES ARE NOT
- 4. CHIPSEAL SURFACE OVER DRIVEWAY TO REDUCE THE NEED FOR WATER BARS.

PERMANENT EROSION CONTROL MEASURES

BEGIN UPON RECEIVING PERMIT(JUNE 2000±). END UPON COMPLETING CONSTRUCTION OF ALL PROJECT

- 3. CULVERTS WITH RSP @ INLET AND OUTLET
- 4. RETAINING WALLS TO REDUCE EXPOSED EARTH SURFACES
- DRIVEWAY ASPHALT PAVEMENT UPON COMPLETION OF FOUNDATION AND FRAMING OF RESIDENCE.
- 6. SILT BASIN.

Winterization Schedule of Parcel 031 Area




NOTES

- 1) REFER TO STORM WATER POLLUTION PREVENTION PLAN (SWPPP) FOR ADDITIONAL INFORMATION PERTAINING TO STORM WATER
- 2) THE LOCATIONS OF TEMPORARY FACILITIES FOR THE CONSTRUCTION OF PHASE I ARE SHOWN FOR CONCEPTUAL PURPOSES. EXACT LOCATIONS SHALL BE DETERMINED IN THE FIELD. TEMPORARY FACILITIES SHALL BE REMOVED UPON COMPLETION OF CONSTRUCTION AND DISTRUBED SOILS SHALL BE REVEGETATED PER THE PROJECT RESTORATIONIST.
- 3) THE DISTURBANCE OF SITE SOILS AND VEGETATION SHALL BE LIMITED TO THE IMMEDIATE AREA OF THE PROPOSED ROAD, HOUSE, WASTE WATER SYSTEM AND PERMITTED IMPROVEMENTS SHOWN ON THESE PLANS. 4) THE CONTRACTOR SHALL REPLACE ALL TREES AND REVEGETATE ANY LOCATIONS OUTSIDE OF THE IMPROVEMENTS SHOWN THAT ARE DAMAGED DURING CONSTRUCTION.
- 4) A COPY OF THE SWPPP DOCUMENT / REPORT SHALL BE KEPT IN THE JOB OFFICE AND COMMUNICATION CENTER ON SITE AT ALL TIMES. THE EROSION CONTROL COMPLIANCE PERSON'S NAME AND PHONE NUMBEE SHALL BE PROVIDED TO THE NAPA COUNTY DEPARTMENT OF PUBLIC WORKS FOR COMPLIANCE WITH THE SWPPP REQUIREMENTS.





Management of Parcel 031 Area






Storm Water Management of Parcel 032 Area







CDF Information of Parcel 031 & 032 Areas (TYP)

Detail C

